



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600145

Date	9/24/2011	Well Owner	Kerr McGee	Well No.	13-7	Lease	GLERRERO
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME #12)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	1007		
Surface	8 5/8" CSG 24"	Bottom of Surface		Fl.	991		
Plug		Plug Landed @	947	Fl.	Time On	0550	
Production		Pipe Landed @	991	Fl.	Plug Down	0730	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE MIKE LINGREEN	620	SKS		
Poz. Mix				
Calcium Chloride User ID ZMOL6	2.5	%		
Gel % Fio-Cete 1/4 WBSW000 2048895 Dr/g				
Mileage Charge	132	Miles		
Fuel Surcharge	132	MILES		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	0642	0648
Disp. Rate	5 BPM	Mixing	0649	0715
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves	0715	0718
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0719	0730
Water/Cement	6.25 Gal/SK			
Water Temp.	59			
Total Slurry Vol.	145.7	BBLS Cement		
Landed Plug @	650	PSI/Final Lift @	200	PSI
Pre-Flush W/	30	BBLS H ₂ O	Tax Reference Code	Sub Total
Displace W/	60.2	BBLS H ₂ O	State	CO 2.9%
Circulate	3	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		44			
1216/1218		Bulk Truck		44/44			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JIM/ADAM/CHRIS

Received By Scott Hancock
Customer or His Agent