

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400255175

Date Received:

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refiling ☐

Sidetrack ☐

PluggingBond SuretyID

20090080

3. Name of Operator: GREAT WESTERN OIL & GAS COMPANY LLC

4. COGCC Operator Number: 10110

5. Address: 700 AUTOMATION DR - UNIT A

City: WINDSOR State: CO Zip: 80550-3119

6. Contact Name: Janni Keidel Phone: (303)398-0388 Fax: (866)742-1784  
Email: jkeidel@gwogco.com

7. Well Name: H-Y Well Number: 20-24

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 7611

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 29 Twp: 6N Rng: 67W Meridian: 6

Latitude: 40.463094 Longitude: -104.919569

Footage at Surface: 740 feet FNL/FSL 1918 feet FEL/FWL FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4784 13. County: WELD

14. GPS Data:

Date of Measurement: 02/07/2012 PDOP Reading: 2.2 Instrument Operator's Name: Robert Kay

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 659 FSL 1964 FWL FWL Bottom Hole: FNL/FSL 659 FSL 1964 FWL FWL  
Sec: 20 Twp: 6N Rng: 67W Sec: 20 Twp: 6N Rng: 67W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 480 ft

18. Distance to nearest property line: 225 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1800 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara-Codell	NB-CD	407-87	80	E/2SW/4-Sec 20

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Township 6 North, Range 67 West, Section 20: S/2 and Section 29: N/2

25. Distance to Nearest Mineral Lease Line: 547 ft

26. Total Acres in Lease: 131

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	854	708	854	0
1ST	7+7/8	4+1/2	11.6	0	7,611	267	7,611	6,817

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments Conductor casing will not be set. Production Casing cement will be minimum 200' above the Niobrara. 30 Day Notice for Rule 305/306 waived in SUA.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Janni Keidel

Title: Permit & Reg Analyst Date: \_\_\_\_\_ Email: jkeidel@gwogco.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### Attachment Check List

Att Doc Num	Name
400257570	LEASE MAP
400257571	WELL LOCATION PLAT
400257573	TOPO MAP
400257831	SURFACE AGRMT/SURETY
400260367	DEVIATED DRILLING PLAN
400260368	DIRECTIONAL DATA

Total Attach: 6 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

### BMP

<u>Type</u>	<u>Comment</u>
Drilling/Completion Operations	<p>Great Western Oil &amp; Gas Company, LLC - Best Management Practices - Summary</p> <p>Storm water management Plans (SWMP) will be in place to address construction, drilling and operations associated with Oil and Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health (CDPHE). BMP's will be constructed around the perimeter of the site prior to or at the beginning of construction; BMP's used will vary according to the location, and will remain in place until the pad reaches final reclamation.</p> <p>Spill Prevention Control and Counter Measures (SPCC) plans will be in place to address any possible spills associated with Oil and Gas operations throughout the state of Colorado in accordance with CFR 112. In accordance with COGCC Rule 1002.f. (2)A. &amp; B., shall provide a designated storage area for dry bulk chemicals and miscellaneous fluids. The storage area shall be covered to prevent contact of precipitation with chemicals, shall be elevated above storm- or standing water, and shall provide sufficient containment to prevent release of spilled fluids or chemicals from impacting soil, surface water or groundwater and will prevent the co-mingling of spilled fluids or chemicals with other E &amp; P Waste.</p> <p>Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup is required to minimize any commingling of waste materials with storm water runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling, There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup will consist of patrolling the roadways, access areas, and other work areas to pick up trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly and promptly.</p>

Total: 1 comment(s)