



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 33120 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 600241

Date <u>11/23/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>15-1</u>	Lease <u>McGee</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil &amp; Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Xtreme "11")</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Ft. <u>890</u>	
(Surface) <u>8 5/8" (56-24")</u>	Bottom of Surface	Ft. <u>882</u>	
Plug	Plug Landed @ <u>838</u>	Ft.	Time On <u>1300</u>
Production	Pipe Landed @ <u>882</u>	Ft.	Plug Down <u>1545</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>✓ Type III 100% Excess</u>	<u>560</u>	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	<u>186</u>	Miles		
Fuel Surcharge	<u>186</u>	Miles		
Additional Cement	<u>80</u>	SKS		
Mixing Rate 4 BPM	Pre-Flush	<u>1501-</u>	<u>1507</u>	
Disp. Rate 5 BPM	Mixing	<u>1507-</u>	<u>1531</u>	
Slurry Vol. 1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves	<u>1531-</u>	<u>1534</u>	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	<u>1534-</u>	<u>1545</u>	
Water/Cement 6.25 Gal/SK				
Water Temp. <u>53°F</u>				
Total Slurry Vol. <u>150.4</u>	BBLs Cement			
Landed Plug @ <u>400</u>	PSI/Final Lift @ <u>200</u>	PSI		
Pre-Flush W/ <u>30</u>	BBLs H <sub>2</sub> O	Tax Reference Code	Sub Total	
Displace W/ <u>53.2</u>	BBLs H <sub>2</sub> O	State <u>CO 2.9%</u>	Tax	
Circulate <u>3</u>	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>60</u>			
<u>1214/1218</u>		Bulk Truck		<u>60/62</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Kenny, Demetrio, Mark

Received By [Signature]  
Customer or His Agent