

FORM
2

Rev
12/05

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400114134

Date Received:

03/03/2011

PluggingBond SuretyID

20030009

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE COMMINGLE

Refiling

Sidetrack

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: MARI CLARK Phone: (303)228-4413 Fax: (303)228-4286

Email: mclark@nobleenergyinc.com

7. Well Name: FRITZLER B Well Number: 02-19

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7000

WELL LOCATION INFORMATION

10. QtrQtr: NWNW Sec: 2 Twp: 5N Rng: 64W Meridian: 6

Latitude: 40.432440 Longitude: -104.522650

Footage at Surface: 1160 feet FNL 1164 feet FWL

11. Field Name: KERSEY Field Number: 44600

12. Ground Elevation: 4630 13. County: WELD

14. GPS Data:

Date of Measurement: 12/17/2010 PDOP Reading: 2.0 Instrument Operator's Name: ROBERT DALEY

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 720 ft

18. Distance to nearest property line: 155 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 706 ft

LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407-87	160	NW/4
NIOBRARA	NBRR	407-87	160	NW/4

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: 20030012

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No: Surface Owners Agreement Attached or \$25,000 Blanket Surface Bond \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

SEE ATTACHED

25. Distance to Nearest Mineral Lease Line: 155 ft 26. Total Acres in Lease: 40

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No

31. Mud disposal: Offsite Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: Land Farming Land Spreading Disposal Facility Other: CLOSED LOOP

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	600	248	600	0
1ST	7+7/8	4+1/2	11.6	0	7,000	621	7,000	

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments NO CONDUCTOR CASING WILL BE USED. 1ST STRING TOP OF CEMENT = 200' ABOVE NIOBRARA.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: MARI CLARK

Title: REG. ANALYST II Date: 3/3/2011 Email: mclark@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 3/30/2011

API NUMBER

05 123 33226 00

Permit Number: _____ Expiration Date: 3/29/2013

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hr notice of spud to Bo Brown at 970-330-6085 or email at bo.brown@state.co.us.
- 2) Set surface casing per Rule 317d, cement to surface. Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC.
- 3) If completed, provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 4) If dry hole, 40 sks cement 50' above Niobrara top, 50 sks cement ½ out, ½ in surface casing, 10 sks cement top of surface casing, cut 4' below GL, weld on plate, 5 sks cement in rat hole & 5 sks cement in mouse hole. Restore surface location.

Attachment Check List

Att Doc Num	Name
1726387	SURFACE CASING CHECK
400114134	FORM 2 SUBMITTED
400138986	WELL LOCATION PLAT
400138987	LEGAL/LEASE DESCRIPTION
400138988	30 DAY NOTICE LETTER

Total Attach: 5 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Changed field to Kersey	3/4/2011 3:34:26 PM

Total: 1 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)