

FORM
5
Rev
02/08

State of Colorado
Oil and Gas Conservation Commission
1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:
400249383

Date Received:
03/01/2012

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type Final completion Preliminary completion

1. OGCC Operator Number: 100185 4. Contact Name: Marina Ayala
 2. Name of Operator: ENCANA OIL & GAS (USA) INC Phone: (720) 876-5905
 3. Address: 370 17TH ST STE 1700 Fax: (720) 876-6905
 City: DENVER State: CO Zip: 80202-

5. API Number 05-045-20782-00 6. County: GARFIELD
 7. Well Name: Federal Smith Well Number: 19-15 (PA-30)
 8. Location: QtrQtr: NENE Section: 30 Township: 7S Range: 95W Meridian: 6
 Footage at surface: Distance: 512 feet Direction: FNL Distance: 429 feet Direction: FEL
 As Drilled Latitude: 39.414237 As Drilled Longitude: -108.031745

GPS Data:
 Date of Measurement: 09/09/2011 PDOP Reading: 4.8 GPS Instrument Operator's Name: Brandon Birdsall

** If directional footage at Top of Prod. Zone Dist.: 536 feet. Direction: FSL Dist.: 1892 feet. Direction: FEL

Sec: 19 Twp: 7S Rng: 95W

** If directional footage at Bottom Hole Dist.: 542 feet. Direction: FSL Dist.: 1916 feet. Direction: FEL

Sec: 19 Twp: 7S Rng: 95W

9. Field Name: PARACHUTE 10. Field Number: 67350

11. Federal, Indian or State Lease Number: COC019572

12. Spud Date: (when the 1st bit hit the dirt) 09/17/2011 13. Date TD: 11/01/2011 14. Date Casing Set or D&A: 11/02/2011

15. Well Classification:
 Dry Oil Gas/Coalbed Disposal Stratigraphic Enhanced Recovery Storage Observation

16. Total Depth MD 6970 TVD** 6527 17 Plug Back Total Depth MD 6891 TVD** 6448

18. Elevations GR 5806 KB 5828 One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:
RST, CBL (same log included in Neutron) and Mud.

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	42	0	40	40	0	40	CALC
SURF	12+1/4	9+5/8	36	0	1,084	361	0	1,100	CALC
1ST	8+3/4	4+1/2	11.60	0	6,941	955	3,614	6,970	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WILLIAMS FORK	3,862	6,731	<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	6,732	6,970	<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Marina Ayala

Title: Permitting Technician Date: 3/1/2012 Email: maraina.ayala@encana.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
400249425	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400249420	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
400249383	FORM 5 SUBMITTED	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400249388	PDF-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400249392	LAS-NEUTRON	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400249400	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400249424	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

User Group	Comment	Comment Date
Permit	off hold. 3/5/12 RST/SM/GR/CCL 2448122 CBL/CBL/VDL/GR/CCL 2448121 MUD 2448123 in scanning	3/8/2012 3:25:03 PM
Permit	on hold pending receipt of paper logs.	3/2/2012 9:59:30 AM

Total: 2 comment(s)