

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400257670

Date Received:

03/06/2012

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 10071

4. Contact Name: Megan Finnegan

2. Name of Operator: BARRETT CORPORATION* BILL

Phone: (303) 299-9949

3. Address: 1099 18TH ST STE 2300

Fax: (303) 291-0420

City: DENVER State: CO Zip: 80202

5. API Number 05-045-19915-00

6. County: GARFIELD

7. Well Name: Kaufman

Well Number: 21D-24-692

8. Location: QtrQtr: SWNE Section: 24 Township: 6S Range: 92W Meridian: 6

Footage at surface: Distance: 1417 feet Direction: FNL Distance: 2247 feet Direction: FEL

As Drilled Latitude: 39.516067 As Drilled Longitude: -107.614184

GPS Data:

Data of Measurement: 12/06/2011 PDOP Reading: 6.0 GPS Instrument Operator's Name: T. Barnett

** If directional footage at Top of Prod. Zone Dist.: 203 feet. Direction: FNL Dist.: 1969 feet. Direction: FWL

Sec: 24 Twp: 6S Rng: 92W

** If directional footage at Bottom Hole Dist.: 190 feet. Direction: FNL Dist.: 1960 feet. Direction: FWL

Sec: 24 Twp: 6S Rng: 92W

9. Field Name: MAMM CREEK

10. Field Number: 52500

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 08/10/2011 13. Date TD: 10/16/2011 14. Date Casing Set or D&A: 10/17/2011

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7858 TVD** 7488 17 Plug Back Total Depth MD 7813 TVD** 7443

18. Elevations GR 5763 KB 5785

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL, Triple Combo, Temperature, Mud

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	42	0	40	0	0	40	CALC
SURF	12+1/4	9+5/8	36	0	791	240	0	810	CALC
1ST	7+7/8	4+1/2	11.6	0	7,857	988	3,120	7,858	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WILLIAMS FORK	3,875		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	7,512		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

The 72 hour Bradenhead Pressure Test was 0 psig. Conductor was cemented with grout. 8 3/4 hole size was used to drill from bottom of surface casing to 5873' then 7 7/8 hole size was drilled to TD.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Megan Finnegan

Title: Permit Analyst Date: 3/6/2012 Email: mfinnegan@billbarrettcorp.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
	CMT Summary *	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400257674	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400257670	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400257671	LAS-TEMPERATURE	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400257672	LAS-TRIPLE COMBINATION	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400257673	LAS-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400257720	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400258405	PDF-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date
------------	---------	--------------

--	--	--

Total: 0 comment(s)