

**FORM
5**Rev
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
Document Number: 400250145			
Date Received: 02/16/2012			

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 100185	4. Contact Name: Marina Ayala
2. Name of Operator: ENCANA OIL & GAS (USA) INC	Phone: (720) 876-5905
3. Address: 370 17TH ST STE 1700	Fax: (720) 876-6905
City: DENVER State: CO Zip: 80202-	

5. API Number 05-045-20664-00	6. County: GARFIELD
7. Well Name: SG	Well Number: 8501E-21 N22496
8. Location: QtrQtr: 5 Section: 22 Township: 4S Range: 96W Meridian: 6	
Footage at surface: Distance: 1334 feet Direction: FSL	Distance: 2006 feet Direction: FWL
As Drilled Latitude: 39.684220	As Drilled Longitude: -108.157018

GPS Data:

Data of Measurement: 08/31/2011 PDOP Reading: 2.0 GPS Instrument Operator's Name: Brandon Birdsall

** If directional footage at Top of Prod. Zone Dist.: 1328 feet. Direction: FNL Dist.: 1147 feet. Direction: FEL

Sec: 21 Twp: 4S Rng: 96W

** If directional footage at Bottom Hole Dist.: 1239 feet. Direction: FNL Dist.: 1439 feet. Direction: FEL

Sec: 21 Twp: 4S Rng: 96W

9. Field Name: WILDCAT	10. Field Number: 99999
11. Federal, Indian or State Lease Number: COC64815	

12. Spud Date: (when the 1st bit hit the dirt) 09/13/2011	13. Date TD: 10/14/2011	14. Date Casing Set or D&A: 10/16/2011
---	-------------------------	--

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 12343 TVD** 11146	17 Plug Back Total Depth MD 12298 TVD** 11101
--------------------------------------	---

18. Elevations GR 7585 KB 7607	One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.
--------------------------------	--

19. List Electric Logs Run:

RST, CBL (included in Triple Combo) and Mud.

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	30	20	53	0	118	242	0	118	CALC
SURF	14+3/4	9+5/8	36	0	2,131	750	0	2,146	CALC
1ST	8+3/4	4+1/2	11.60	0	12,323	1,895	930	12,343	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WILLIAMS FORK	8,347	12,227	<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	12,228	12,343	<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Marina Ayala

Title: Permitting Technician Date: 2/16/2012 Email: marina.ayala@encana.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400250166	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400250167	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400250145	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400250159	PDF-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400250161	LAS-TRIPLE COMBINATION	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400250168	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date
Permit	off hold--oper. submitted PDOP value.	3/6/2012 2:02:46 PM
Permit	on hold pending receipt of PDOP value	3/6/2012 1:37:16 PM

Total: 2 comment(s)