

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400254791

Date Received:

03/01/2012

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 100322

4. Contact Name: EILEEN ROBERTS

2. Name of Operator: NOBLE ENERGY INC

Phone: (303) 2284330

3. Address: 1625 BROADWAY STE 2200

Fax: (303) 2284286

City: DENVER State: CO Zip: 80202

5. API Number 05-123-33576-00

6. County: WELD

7. Well Name: 70 RANCH BB

Well Number: 21-65HN

8. Location: QtrQtr: NWSW Section: 21 Township: 5N Range: 63W Meridian: 6

Footage at surface: Distance: 2569 feet Direction: FSL Distance: 69 feet Direction: FWL

As Drilled Latitude: 40.384820 As Drilled Longitude: -104.450310

GPS Data:

Data of Measurement: 08/16/2011 PDOP Reading: 4.8 GPS Instrument Operator's Name: Paul Tappy

** If directional footage at Top of Prod. Zone Dist.: 2592 feet. Direction: FSL Dist.: 666 feet. Direction: FWL

Sec: 21 Twp: 5N Rng: 63W

** If directional footage at Bottom Hole Dist.: 2616 feet. Direction: FNL Dist.: 540 feet. Direction: FEL

Sec: 21 Twp: 5N Rng: 63W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 07/22/2011 13. Date TD: 07/22/2011 14. Date Casing Set or D&A: 07/30/2011

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 10856 TVD** 6418 17 Plug Back Total Depth MD 10840 TVD** 6402

18. Elevations GR 4636 KB 4660

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL/GRL/CCL/VDL.

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	13+3/4	9+5/8	36.00	24	618	357	0	628	CALC
1ST	8+3/4	7+0/0	26.00	24	6,770	555	320	6,780	CBL
1ST LINER	6+1/8	4+1/2	11.60	5660	10,850	0	0	10,850	

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SUSSEX	4,159		<input type="checkbox"/>	<input type="checkbox"/>	
SHANNON	4,732		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	6,651		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Eileen Roberts

Title: Regulatory Specialist

Date: 3/1/2012

Email: eroberts@nobleenergyinc.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400254845	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400254846	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400254791	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400257071	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date
Permit	Operator stated MWD log sent 3/13/2012	3/13/2012 11:32:00 AM
Permit	Requested MWD log.	3/9/2012 8:02:02 AM

Total: 2 comment(s)