

Kubeczko, Dave

From: Kubeczko, Dave
Sent: Wednesday, March 14, 2012 1:33 PM
To: Kubeczko, Dave
Subject: FW: SG Interests I, ECK 12-90-1 #1 Pad, Lot 1 Sec 1 T12S R90W, Gunnison County, Form 2A (#2286782) CPW Correspondence

Categories: Dark Green - CDOW Pass, Orange - Operator Correspondence

Scan No 2034178

CPW CORRESPONDENCE

2A#2286782

From: Catherine Dickert [<mailto:cdickert@sginterests.com>]
Sent: Tuesday, March 13, 2012 1:53 PM
To: Kubeczko, Dave
Cc: Eric Sanford
Subject: Eck 12-90-1 #1

Dave,

SG Interests agrees to use the CPW-recommended wildlife friendly seed mix for reclamation activities on the Eck 12-90-1 #1 well project.

SG Interests is currently discussing a possible Wildlife Mitigation Plan with CPW. Our next meeting with CPW on this topic is scheduled for March 15, 2012.

Please contact me with any questions. Thank you.

Catherine Dickert
Environmental and Permitting Manager
SG Interests, I Ltd.
1065 Main Avenue, Suite 209
Durango, CO 81301

Phone: 970-209-6464
Fax: 970-252-0636

cdickert@sginterests.com

MUDDY CREEK WILDLIFE FRIENDLY SEED MIX SHEET is attached:

Muddy Creek Wildlife Friendly Seed Mix Sheet

Ecotype: Oakbrush/Mountain shrublands

Species *recommended variety unless locally collected seed is available, in which case locally collected seed is preferred

GRASSES Variety* % of mix FRPLS* PLS rate/acre *based on drill seeding; 2x if broadcasting

Slender wheatgrass	San Luis	15%	6	0.9
Western wheatgrass	Arriba	10%	8	0.8
Bluebunch wheatgrass	Secar/Goldar	15%	10	1.5
Idaho fescue		10%	4	0.4
Muttongrass	(UP Colona)	15%	1	0.15
Junegrass	Uncomprahgre	15%	4	0.6
Sandberg bluegrass	"UP release"	10%	2	0.2
Green needlegrass		10%	8	0.8
Mountain brome	Garnet	10%	12	1.2
		1.1		

FORBS Variety

Utah sweetvetch	(UP Uncompahgre) TII	15%	15	2.25	*Select 5 of the 8 species based on availability
Lewis flax	Maple grove	15%	4	0.6	
Penstemon comarrhenus* (dusty)	(UP Delta)	15%	1	0.15	
Penstemon cyanocaulis* (bluestem)	(UP San Miguel)	15%	1	0.15	
Penstemon palmeri* (palmer)		15%	2	0.3	
Penstemon strictus* (Rocky Mtn)		15%	1	0.15	
Silky lupine -sericeus		15%	20	3	
American vetch		15%	25	3.75	
Oregon daisy	(UP Dry Fork)	15%	1	0.15	

(Alfalfa) Ladak () these species are included to enhance the initial value of the seeding for big game; include in addition to the 5 native forbs

(Small burnet)

(Sainfoin)

SHRUBS* Variety

Antelope bitterbrush		1	*Select 3 of the 4 species based on availability
Mtn. mahogany		1	
Artemisia tridentata ssp. vaseyana		1	
Utah serviceberry		1	

NOTE: (UP)- The UP varieties are recently released and may not be available in sufficient quantities. Supply and availability may increase in future years