



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 600236

Date <b>11-24-11</b>	Well Owner <b>Kerr McGee</b>	Well No. <b>37-12</b>	Lease <b>RIVERBEND</b>
County <b>WELD</b>	State <b>Colorado</b>		
Charge to <b>Kerr McGee Oil &amp; Gas Onshore, LP</b>			
Address <b>1999 Broadway, Suite 3700 (XTREME #15)</b>			
City, State Zip <b>Denver, Colorado 80202</b>			
Type of Job <b>Surface</b>	Depth <b>1042</b>		
<b>8 5/8" CSG-24#</b>	Bottom of Surface <b>1037</b>		
Plug	Plug Landed @ <b>992</b>	Ft. Time On <b>2000</b>	
Production	Pipe Landed @ <b>1037</b>	Ft. Plug Down <b>2345</b>	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <b>TYPE III</b>	<b>1650</b>	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % - Flo-Crete 1/4 # Per Sack				
Mileage Charge	<b>204</b>	Miles		
Fuel Surcharge	<b>204</b>	MILES		
Additional Cement		SKS		
Mixing Rate <b>4 BPM</b>	Pre-Flush <b>2242</b>	<b>2250</b>		
Disp. Rate <b>5 BPM</b>	Mixing <b>2250</b>	<b>2329</b>		
Slurry Vol. <b>1.32<sup>3</sup> Cu.Ft./Sk</b>	Change Valves <b>2329</b>	<b>2332</b>		
Slurry Wt. <b>14.8 - 15.0 PPG</b>	Displacement <b>2332</b>	<b>2345</b>		
Water/Cement <b>6.25 Gal/SK</b>				
Water Temp <b>50 °F</b>				
Total Slurry Vol. <b>152.8</b>	BBLs Cement			
Landed Plug @ <b>300</b>	PSI/Final Lift @ <b>280</b>	PSI		
Pre-Flush Wt <b>30</b>	BBLs H <sub>2</sub> O	Tax Reference Code	Sub Total	
Displace Wt <b>63.0</b>	BBLs H <sub>2</sub> O	State <b>CO 2.9%</b>	Tax	
Circulate <b>3</b>	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<b>1302</b>		Pump Truck		<b>68</b>			
<b>1214/1216</b>		Bulk Truck		<b>68168</b>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **JOE, JOSH, EVAN, ERNIE**

Received By **M. H. H. H.**  
Customer or His Agent