



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600192

Date	11/13/2011	Well Owner	Kerr McGee	Well No.	38-12	Lease	RIVERBEND
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME #15)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		FL	1020		
Surface	8 5/8" CSG 24"	Bottom of Surface		FL	1014		
Plug		Plug Landed @	970	FL	Time On	1620	
Production		Pipe Landed @	1014	FL	Plug Down	0130	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	640	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack	204/012.021			
Mileage Charge	204	Miles		
Fuel Surcharge	204	MILES		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	0034	0038
Disp. Rate	5 BPM	Mixing	0038	0115
Slurry Vol.	1.32 Cu.Ft./Sk.	Change Valves	0115	0118
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0118	0130
Water/Cement	6.25 Gal/SK			
Water Temp.	67			
Total Slurry Vol.	150.4	BBLs Cement		
Landed Plug @	380	PSI/Final Lift @	125	PSI
Pre-Flush W/	20	BBLs H ₂ O	Tax Reference Code	Sub Total
Displace W/	61.6	BBLs H ₂ O	State	CO 2.9%
Circulate	5	BBLs Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		68			
1217/1214		Bulk Truck		68/68			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JIM ADAM/CHAS

Received By CODY SANDERS
Customer or His Agent