

Well : CRANDELL 0-8-26  
Field : WATTENBERG  
County : BROOMFIELD State : Colorado  
Surface : 1715 FSL, 1008' FWL, NWSW Sec 26-T1N-R68W  
:  
:  
Grd Elev : 5217' GR KB Elev : 5230' KB

Well History:

Spud 10-04-2011  
TD 10-08-2011

Log Tops:

Sussex 5222'  
Niobrara 7984'  
Codell 8411'  
J Sand 8848'

Surface Casing and Cement

8-5/8", Set @ 1061'  
Cemented with 390'

Production Casing and Cement

4-1/2" production casing set @ 8967'  
Cemented with 670 sxs

CBP

Set @ 7940'. 02-10-12  
Drilled out on 02-11-12

Perf'd the Niobrara 7992' - 8210' @ 4 spf  
Frac'd the Niobrara 7992' - 8210' (176 holes), w/ 99,708  
gals 18 # Vistar Hybrid cross linked gel containing 250,020#  
30/50 sand. 11-22-11

CFP

Set @ 8250'. 11-22-11  
Drilled out on 02-11-12  
Perf'd the Codell from 8411' - 8424' @ 2 spf  
Frac'd the Codell 8411' - 8424', (26 holes) w/ 88,410  
gal 22 # Vistar Hybrid cross linked gel containing  
251,600 # 30/50 sand. 11-22-11

CFP

Set @ 8460'. 11-22-11  
Drilled out on 02-11-12  
Perf'd the J Sand from 8861' - 8878' @ 2 spf  
Frac'd the J-Sand 8861' - 8878', (34 holes) w/ 62,580 gal  
18 # Vistar Hybrid cross linked gel containing 249,980#  
20/40 Sand. 11-22-11

Production Tubing

2-3/8", Set @ 8824.86'

TD 8980'

Drawn by:

Sheilla Reed-High