

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400262329

Date Received:

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

PluggingBond SuretyID

20090078

3. Name of Operator: PETROLEUM DEVELOPMENT CORPORATION

4. COGCC Operator Number: 69175

5. Address: 1775 SHERMAN STREET - STE 3000

City: DENVER State: CO Zip: 80203

6. Contact Name: Liz Lindow Phone: (303)831-3974 Fax: ()

Email: llindow@petd.com

7. Well Name: Spaur Well Number: 31W-214

8. Unit Name (if appl): Wattenberg Unit Number: 90750

9. Proposed Total Measured Depth: 11131

WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 31 Twp: 7N Rng: 63W Meridian: 6

Latitude: 40.533880 Longitude: -104.471230

Footage at Surface: 1324 feet FNL/FSL FNL 250 feet FEL/FWL FEL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4756 13. County: WELD

14. GPS Data:

Date of Measurement: 02/16/2012 PDOP Reading: 2.7 Instrument Operator's Name: Wyatt Hall

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1830 FNL 500 FEL 1830 FNL 500 FWL FWL  
Sec: 31 Twp: 7N Rng: 63W Sec: 31 Twp: 7N Rng: 63W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 253 ft

18. Distance to nearest property line: 250 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 11 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR		160	S2N2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 19990086

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

N2 of Sec 31 T7N R63W

25. Distance to Nearest Mineral Lease Line: 500 ft

26. Total Acres in Lease: 320

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: closed loop

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	875	730	875	0
1ST	8+3/4	7+0/0	26	0	7,249	650	7,249	600
1ST LINER	6+1/8	4+1/2	11.6	6047	11,131			

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments Conductor casing will not be used. Conductor casing will not be used. Operator requests an exception location per rule 318Aa and rule 318Ac: well will not be drilled in a legal drilling window or twinned with an existing well. Waviers attached. Per rule 318Ae, the Operator requests the proposed spacing unit consisting of 160 acres, S2N2 of Sec 31 T7N R63W. Proposed spacing unit map and 30-day certificate is attached.

34. Location ID: 426149

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Liz Lindow

Title: Permit Representative Date: \_\_\_\_\_ Email: llindow@petd.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### Attachment Check List

Att Doc Num	Name
400262330	DIRECTIONAL DATA
400262334	DEVIATED DRILLING PLAN
400262335	WELL LOCATION PLAT
400262337	CORRESPONDENCE
400262338	PROPOSED SPACING UNIT
400262339	TOPO MAP
400262340	30 DAY NOTICE LETTER
400262341	EXCEPTION LOC REQUEST
400262342	EXCEPTION LOC WAIVERS

Total Attach: 9 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

### BMP

<u>Type</u>	<u>Comment</u>
Drilling/Completion Operations	<p>Anti-Collision</p> <p>Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5.</p>

Total: 1 comment(s)