

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400241011

Date Received:

02/28/2012

PluggingBond SuretyID

20070004

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: BONANZA CREEK ENERGY OPERATING COMPANY LLC

4. COGCC Operator Number: 8960

5. Address: P O BOX 21974

City: BAKERSFIELD State: CA Zip: 93390

6. Contact Name: Keith Caplan Phone: (720)440-6100 Fax: (720)279-2331

Email: KCaplan@bonanzacrk.com

7. Well Name: Antelope Well Number: H-31

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 6866

WELL LOCATION INFORMATION

10. QtrQtr: SENW Sec: 31 Twp: 5N Rng: 62W Meridian: 6

Latitude: 40.356780 Longitude: -104.366280

Footage at Surface: 2392 feet FNL/FSL FNL 2543 feet FEL/FWL FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4590 13. County: WELD

14. GPS Data:

Date of Measurement: 12/19/2011 PDOP Reading: 1.9 Instrument Operator's Name: Wyatt Hall

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2530 FNL 1200 FWL 2530 FNL 1200 FWL
Bottom Hole: FNL/FSL 2530 FNL 1200 FWL
Sec: 31 Twp: 5N Rng: 62W Sec: 31 Twp: 5N Rng: 62W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 5280 ft

18. Distance to nearest property line: 2392 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 738 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara-Codell	NB-CD		160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Please See Attached.

25. Distance to Nearest Mineral Lease Line: 1200 ft

26. Total Acres in Lease: 9046

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	410	170	410	0
1ST	7+7/8	4+1/2	11.6	0	6,836	159	6,866	5,986

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments Conductor casing will not be used on this well. Wellbore Spacing Unit: T5N62W: Sec 31 S/2NW/4 and N/2SW/4. Wellhead is to be located outside of a GWA drilling window and will be located more than 50' from an existing well location. Bonanza Creek requests an exception location to 318Aa, 318Ac: Exception request and waiver attached.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Keith Caplan

Title: Sr. Operations Tech Date: 2/28/2012 Email: KCaplan@bonanzacrk.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 3/23/2012

API NUMBER

05 123 35303 00

Permit Number: _____ Expiration Date: 3/22/2014

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 48 hour notice of MIRU to John Montoya by e-mail at John.Montoya@state.co.us. Indicate Spud Notice in the subject line and provide the following information: Operator Name, Well Name and Number, API #, Spud Date, Contact Name, Contact Phone #, Email Address. Submit Form 42 electronically after April 1 for spud notice.
- 2) Provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 3) Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Operator must meet water well sampling requirements as per Rule 318A.

Attachment Check List

Att Doc Num	Name
2331823	SURFACE CASING CHECK
2531981	EXCEPTION LOC REQUEST
2531983	EXCEPTION LOC WAIVERS
400241011	FORM 2 SUBMITTED
400243659	DIRECTIONAL DATA
400243660	DEVIATED DRILLING PLAN
400243661	PLAT
400243663	PROPOSED SPACING UNIT
400243664	PROPOSED SPACING UNIT
400243665	LEGAL/LEASE DESCRIPTION
400255833	SURFACE AGRMT/SURETY

Total Attach: 11 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	No LGD or public comment received; final review completed.	3/22/2012 10:37:44 AM
Permit	Updated permit with request and waiver.	2/28/2012 10:42:27 AM
Permit	Surface location is not within the drilling window. Nee exception request letter and waiver.	2/28/2012 8:12:08 AM

Total: 3 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)