

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400217414

Date Received:

02/29/2012

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE COMMINGLE

Refiling
Sidetrack

PluggingBond SuretyID

20100017

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: MIRACLE PFISTER Phone: (720)876-3761 Fax: (720)876-4861

Email: miracle.pfister@encana.com

7. Well Name: MCU FEE Well Number: 22-12B (N22W)

8. Unit Name (if appl): MIDDLETON CREEK Unit Number: COC068997

9. Proposed Total Measured Depth: 9643

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 22 Twp: 7S Rng: 93W Meridian: 6

Latitude: 39.425892 Longitude: -107.762036

Footage at Surface: 653 feet FNL/FSL FSL 2080 feet FEL/FWL FWL

11. Field Name: MAMM CREEK Field Number: 52500

12. Ground Elevation: 7026 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 05/18/2011 PDOP Reading: 0.0 Instrument Operator's Name: TED TAGGART

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1950 FSL 730 FWL 1950 FSL 730 FWL
Bottom Hole: FNL/FSL 1950 FSL 730 FWL
Sec: 22 Twp: 7S Rng: 93W Sec: 22 Twp: 7S Rng: 93W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 2100 ft

18. Distance to nearest property line: 481 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 310 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ILES	ILES			
WILLIAMS FORK	WMFK			

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No: Surface Owners Agreement Attached or \$25,000 Blanket Surface Bond \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T7S-R93W SEC 10: S2SW, N2SE, SESE SEC 11: SWNW, W2SW, SESW SEC 14: S2NE, E2W2, SE SEC 15: W2, SWSE, W2SE
SEC 16: E2NE SEC 22: NWNW, E2NW, N2SW

25. Distance to Nearest Mineral Lease Line: 683 ft 26. Total Acres in Lease: 1480

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No

31. Mud disposal: Offsite Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: Land Farming Land Spreading Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	20	16	LINEPIPE	0	40	5	40	0
SURF	12+1/4	9+5/8	36	0	1,446	446	1,446	0
1ST	7+7/8	4+1/2	11.6	0	9,626	776	9,626	0

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments THE NEAREST DISTANCE IS TO A ABOVE GROUND UTILITY. TOP OF PRODUCTION CEMENT WILL BE 200' ABOVE MSVD. ATTACHED IS AN APPROVED SUNDRY FOR SURFACE OCCUPANCY FROM THE BLM.

34. Location ID: 324286

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: MIRACLE PFISTER

Title: REGULATORY ANALYST Date: 2/29/2012 Email: miracle.pfister@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 3/23/2012

API NUMBER

05 045 21455 00

Permit Number: _____ Expiration Date: 3/22/2014

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.
- 2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE
- 3) NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE
- 4) COMPLIANCE WITH THE NOTICE TO OPERATORS DRILLING WELLS IN THE BUZZARD, MAMM CREEK, AND RULISON FIELDS, GARFIELD COUNTY AND MESA COUNTY – PROCEDURES AND SUBMITTAL REQUIREMENTS FOR COMPLIANCE WITH COGCC ORDER NOS. 1-107, 139-56, 191-22, AND 369-2 (JULY 8, 2010) -- IS REQUIRED. SEE ATTACHED NOTICE.
- 5) CEMENT ON PRODUCTION CASING MUST BE A MINIMUM OF 200' ABOVE THE TOP OF THE MESA VERDE FORMATION (OR 200' ABOVE THE OHIO CREEK FORMATION IF PRESENT). CEMENT TOP VERIFY BY CBL IS REQUIRED. THIS REQUIREMENT SHALL SUPERSEDE THE TOP OF CEMENT REQUIREMENTS IN THE NEW MAMM CREEK FIELD NOTICE TO OPERATORS.
- 6) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

Attachment Check List

Att Doc Num	Name
400217414	FORM 2 SUBMITTED
400256652	SURFACE AGRMT/SURETY
400256653	WELL LOCATION PLAT
400256655	DEVIATED DRILLING PLAN
400256656	DIRECTIONAL DATA

Total Attach: 5 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	This APD was waiting on BLM ROW; attached. LGD passed/public comments waived. Final Comprehensive Review Status-passed.	3/21/2012 11:10:09 AM
Permit	ready to approve. 2A and other APD's on pad approved 2/29/2011.	3/5/2012 1:09:47 PM
LGD	Passed	3/5/2012 9:39:53 AM

Total: 3 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)