

Well Name:		Miller Federal 24B-31-691		BILL BARRETT CORPORATION	
SHL:		NWSE Sec. 6 T6S, R91W 6th PM		date updated 3/22/2012	
				updated by Brady Riley	
05-045-18658				AS DRILLED	
<div><div><div>Top of lead @ surface</div><div>9.625", 36 lbs/ft, J-55</div></div><div><div>Mesaverde</div><div>3330 MD3154 TVD</div></div><div><div>Top of Gas</div><div>4865 MD4456 TVD</div></div><div><div>Cementing Program:</div><div>Surface:<div>Lead: 120 sks</div><div>Tail: 120 sks</div></div><div>Production:<div>Tail: 1005 sks</div></div></div><div><div>Rollins</div><div>7046 MD6820 TVD</div></div><div><div>TD</div><div>7340 MD7114 TVD</div></div><div>NOT TO SCALE</div></div> <div><div>12-1/4" Hole</div><div>SPUD 7/7/2010</div><div>TD 12/17/2010</div><div>set @ 771</div><div>Drilled 8 3/4" hole from base surface casing to 4956 MD then drilled 7 7/8" hole to TD</div><div>Top of tail cement @ 2270 MD0 TVD</div><div>set @ 7334 MD</div></div>					