

FORM
5

Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

2591565

Date Received:

12/07/2010

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 77330

4. Contact Name: DIANE MCCALLUM

2. Name of Operator: SG INTERESTS I LTD

Phone: (970) 252-0696

3. Address: PO BOX 26

Fax: (970) 252-0636

City: MONTROSE State: CO Zip: 81402

5. API Number 05-051-06094-00

6. County: GUNNISON

7. Well Name: COW SKULL 11-89-18

Well Number: 1

8. Location: QtrQtr: NESW Section: 18 Township: 11S Range: 89W Meridian: 6

Footage at surface: Distance: 1991 feet Direction: FSL Distance: 1760 feet Direction: FWL

As Drilled Latitude: As Drilled Longitude:

GPS Data:

Data of Measurement: PDOP Reading: GPS Instrument Operator's Name:

** If directional footage at Top of Prod. Zone Dist.: feet. Direction: Dist.: feet. Direction:

Sec: Twp: Rng:

** If directional footage at Bottom Hole Dist.: feet. Direction: Dist.: feet. Direction:

Sec: Twp: Rng:

9. Field Name: WILDCAT

10. Field Number: 99999

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 08/29/2010 13. Date TD: 11/03/2010 14. Date Casing Set or D&A: 11/05/2010

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 8959 TVD** 17 Plug Back Total Depth MD 8953 TVD**

18. Elevations GR 7387 KB 7409

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

TRIPLE COMBO, TIF.CBL, FMI DSLT SONIC, MUD LOG

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	36	20		0	80	84	0	80	CALC
SURF	16	13+3/8		0	441	197	0	441	CALC
1ST	12+1/4	9+5/8		0	5,277	380	3,000	5,277	CBL
2ND	8+1/2	7		0	8,953	382	5,077	8,959	CALC

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
DV TOOL	2ND	6,854	178		6,854
DV TOOL	1ST	3,315	664		3,315
SQUEEZE	1ST	5,200	150		5,277

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
COAL	3,042		<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO COAL	3,872		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	3,967		<input type="checkbox"/>	<input type="checkbox"/>	
COZZETTE	4,815		<input type="checkbox"/>	<input type="checkbox"/>	
CORCORAN	4,962		<input type="checkbox"/>	<input type="checkbox"/>	
MANCOS	5,109		<input type="checkbox"/>	<input type="checkbox"/>	
DAKOTA	8,933		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: DIANE MCCALLUM

Title: COMPLIANCE & REGULATORY Date: 12/2/2010 Email: DMCCALLUM@SGINTERESTS.COM

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
2591566	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Directional Survey **	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
2591565	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	REQ AS DRILLED GPS	5/4/2011 9:06:37 AM
Data Entry	UNREGOGNIZED FORMATION NAME W/MEASURED DEPTH: SOUTH CANYON V-SEAM 3455'	3/1/2011 7:41:55 AM

Total: 2 comment(s)