



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600199

Date	11/23/11	Well Owner	Kerr McGee	Well No.	3N-25 HZ	Lease	Camp
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (Major R.J. 44)						
City, State Zip	Denver, Colorado 80202						
Type of Job			Depth	874			
Surface	9 5/8 CS 36" 12 1/4" Hole		Bottom of Surface	869			
Plug			Plug Landed @	825		Time On	0230
Production			Pipe Landed @	869		Plug Down	0700

Description	Qty.	Meas.	
Set Up Charge	1		
Cement Neat Type III	420	SKS	
Poz. Mix			
Calcium Chloride	2.5	%	
Gel % Flo-Cete 1/4 # Per Sack			
Mileage Charge	2061537. DRL	132	Miles
Fuel Surcharge	80012090	132	miles
Additional Cement		SKS	
Mixing Rate	4 BPM	Pre-Flush	0617 0621
Disp. Rate	5 BPM	Mixing	0621 0645
Slurry Vol.	1.32 Cu. Ft./Sk	Change Valves	0645 0648
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0648 0700
Water/Cement	6.25 Gal/SK		
Water Temp.	55°F		
Total Slurry Vol.	98.7	BBLS Cement	
Landed Plug @	850	PSI/Final Lift @	PSI
Pre-Flush W/	20	BBLS H ₂ O	Tax Reference Code
Displace W/	63.5	BBLS H ₂ O	State CO 2.9%
Circulate	4	BBLS Cement	Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		44			
1217/1216		Bulk Truck		44/44			