

**FORM
5**Rev
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400264275

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 61250

4. Contact Name: MARK SHREAVE

2. Name of Operator: MULL DRILLING COMPANY INC

Phone: (316) 264-6366

3. Address: 1700 N WATERFRONT PKWY B#1200

Fax: (316) 264-6440

City: WICHITA State: KS Zip: 67206-

5. API Number 05-061-06869-00

6. County: KIOWA

7. Well Name: TSA UNIT

Well Number: 1-14

8. Location: QtrQtr: SWNW Section: 14 Township: 17S Range: 45W Meridian: 6

Footage at surface: Distance: 2150 feet Direction: FNL Distance: 171 feet Direction: FWL

As Drilled Latitude: 38.578810 As Drilled Longitude: -102.434700

GPS Data:

Data of Measurement: 03/20/2012 PDOP Reading: 2.7 GPS Instrument Operator's Name: KEITH WESTFALL

** If directional footage at Top of Prod. Zone Dist.: feet. Direction: Dist.: feet. Direction:

Sec: Twp: Rng:

** If directional footage at Bottom Hole Dist.: feet. Direction: Dist.: feet. Direction:

Sec: Twp: Rng:

9. Field Name: WILDCAT

10. Field Number: 99999

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 02/18/2012 13. Date TD: 03/02/2012 14. Date Casing Set or D&A: 03/03/2012

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 5300 TVD** 17 Plug Back Total Depth MD 5285 TVD**

18. Elevations GR 4129 KB 4140

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CDL/CNL/PE
DIL
SONIC
MEL

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24	0	352	265	0	352	CALC
1ST	7+7/8	5+1/2	17	0	5,287	225	3,380	5,287	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: 03/15/2012

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
STAGE TOOL	STAGE TOOL	2,669	325	0	2,669

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SHAWNEE	3,772		<input type="checkbox"/>	<input type="checkbox"/>	
HEEBNER	3,970		<input type="checkbox"/>	<input type="checkbox"/>	
LANSING	3,996		<input checked="" type="checkbox"/>	<input type="checkbox"/>	
MARMATON	4,404		<input checked="" type="checkbox"/>	<input type="checkbox"/>	
FORT SCOTT	4,470		<input type="checkbox"/>	<input type="checkbox"/>	
CHEROKEE	4,533		<input type="checkbox"/>	<input type="checkbox"/>	
ATOKA	4,674		<input type="checkbox"/>	<input type="checkbox"/>	
MORROW	4,806		<input type="checkbox"/>	<input type="checkbox"/>	
KEYES	4,904		<input type="checkbox"/>	<input type="checkbox"/>	
MISSISSIPPIAN	4,985		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: MARK SHREVE

Title: PRESIDENT

Date: _____

Email: MSHREVE@MULLDRILLING.COM

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400265409	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Directional Survey **	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400265407	DST Analysis	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>

General Comments**User Group****Comment****Comment Date**

--	--	--

Total: 0 comment(s)