

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400257579

Date Received:

03/02/2012

PluggingBond SuretyID

20060159

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER ☐
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: BLACK RAVEN ENERGY INC

4. COGCC Operator Number: 10203

5. Address: 1331 17TH STREET - #350

City: DENVER State: CO Zip: 80202

6. Contact Name: JANICE ALDSTADT Phone: (303)308-1330 Fax: (303)308-1590

Email: jaldstadt@blackravenenergy.com

7. Well Name: LELAND TRUST Well Number: 843-29-43

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 3000

WELL LOCATION INFORMATION

10. QtrQtr: NESE Sec: 29 Twp: 8N Rng: 43W Meridian: 6

Latitude: 40.634820 Longitude: -102.165790

Footage at Surface: 2143 feet FNL/FSL 238 feet FEL/FWL FEL

11. Field Name: WILDCAT Field Number: 99999

12. Ground Elevation: 3655 13. County: PHILLIPS

14. GPS Data:

Date of Measurement: 02/16/2012 PDOP Reading: 2.6 Instrument Operator's Name: KEVIN MCCORMICK

15. If well is ☐ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

Sec: Twp: Rng: Sec: Twp: Rng:

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 208 ft

18. Distance to nearest property line: 238 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1253 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #:

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T8N-R43W SECTION 8: NW/4, SECTION 29: S/2

25. Distance to Nearest Mineral Lease Line: 238 ft

26. Total Acres in Lease: 480

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: EVAP & BURIAL

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	9+7/8	7+0/0	17	12	450	180	450	0
1ST	6+1/4	4+1/2	10.5	0	3,000	80	3,000	1,600

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments No conductor casing will be used. The perforated interval is estimated to be shallower than 2,500 feet.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JANICE ALDSTADT

Title: LANDMAN Date: 3/2/2012 Email: jaldstadt@blackravenenergy.co

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 3/30/2012

API NUMBER

05 095 06458 00

Permit Number: _____ Expiration Date: 3/29/2014

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 48 hour notice of MIRU via Form 42 electronically after April 1 for spud notice.
 - 2) Set surface casing at least 50' into Pierre Shale for aquifer coverage, (450' minimum - as proposed).
 - 3) If completed, provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
 - 4) If dry hole, set 35 sks cement 50' above Niobrara top, 35 sks cement ½ out, ½ in surface casing, 10 sks cement at top of surface casing, cut casing 4' below GL, weld on plate, 5 sks cement in rat hole & 5 sks cement in mouse hole.
- Well cannot be completed at a depth of 2500 feet or greater.

Attachment Check List

Att Doc Num	Name
2331974	SURFACE CASING CHECK
400257579	FORM 2 SUBMITTED
400257586	WELL LOCATION PLAT
400257587	TOPO MAP

Total Attach: 4 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	No LGD or public comment received; final review completed.	3/28/2012 6:24:40 AM

Total: 1 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)