

Jepsen 23A-2 Proposed P&A WBD

Welded Cap on surface casing

Cement behind surface casing from 646'
to surface

Cement inside 7" casing from 1320' to
surface

Bottom of surface 9-5/8" casing (646')

Multiple Perf intervals:

828 - 832

972 - 976

1030 - 1034

1044 - 1052

1076 - 1082

1174 - 1182

1210 - 1216

1228 - 1232

Bottom of cement plug inside 7" casing
(1320')

Float Collar 1423'

Cement behind 7" casing from 1466' to
surface

TD 1466'

