

FORM

2

Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400267816

Date Received:

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
 SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐Sidetrack ☐

PluggingBond SuretyID

20010124

3. Name of Operator: KERR-MCGEE OIL &amp; GAS ONSHORE LP

4. COGCC Operator Number: 47120

5. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-3779

6. Contact Name: Rebecca Heim Phone: (720)929-6361 Fax: (720)929-7361

Email: rebecca.heim@anadarko.com

7. Well Name: NILES Well Number: 29C-28HZ

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 12012

## WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 28 Twp: 3N Rng: 66W Meridian: 6

Latitude: 40.189255 Longitude: -104.789968

Footage at Surface: 210 feet FNL/FSL FSL 457 feet FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4934.6 13. County: WELD

## 14. GPS Data:

Date of Measurement: 03/15/2012 PDOP Reading: 1.5 Instrument Operator's Name: ROB WILSON

15. If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
 625 FSL 1430 FWL 460 FNL 1430 FWL  
 Sec: 28 Twp: 3N Rng: 66W Sec: 28 Twp: 3N Rng: 66W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 213 ft

18. Distance to nearest property line: 203 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 113 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL		320	W/2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Please see attached Oil and Gas Lease.

25. Distance to Nearest Mineral Lease Line: 0 ft

26. Total Acres in Lease: 640

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	13+1/2	9+5/8	36.0	0	900	670	900	0
1ST	8+3/4	7	26.0	0	7,812	750	7,812	
1ST LINER	6+1/8	4+1/2	11.6	6795	12,012		12,012	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments No conductor casing will be used/The surface location of this well is an exception to Rule 318A.a and to Rule 318A.c. This well is not within the GWA surface location window and does not meet the twinning requirement due to the number of wells planned for this area and at the request of the surface owner. An exception location request letter and signed waivers are attached to the Form 2 and Form 2A/Kerr-McGee Oil & Gas Onshore LP ("KMG") respectfully requests the Director to waive Rule 318A.m for this well. KMG is the operator of the encroached upon well(s).

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Rebecca Heim

Title: Regulatory Analyst II Date: \_\_\_\_\_ Email: DJRegulatory@anadarko.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### **Attachment Check List**

Att Doc Num	Name
400267822	DEVIATED DRILLING PLAN
400267823	PLAT
400267824	TOPO MAP
400267825	30 DAY NOTICE LETTER
400267826	SURFACE AGRMT/SURETY
400267827	OIL & GAS LEASE
400267828	EXCEPTION LOC REQUEST
400267829	EXCEPTION LOC WAIVERS
400267830	VARIANCE REQUEST
400267831	PROPOSED SPACING UNIT
400267832	OTHER
400268399	DIRECTIONAL DATA

Total Attach: 12 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>

Total: 0 comment(s)

## BMP

<u>Type</u>	<u>Comment</u>
Drilling/Completion Operations	<p>1. At least seven (7) days prior to fracture stimulation, the operator is to notify all operators of non-operated wells within 300 feet of the wellbore to be fracture stimulated of the anticipated date stimulation date and the recommended best management practice to shut-in all wells within 300' of the stimulated wellbore completed in the same formation.</p> <p>2. The operator will monitor the bradenhead pressure of all wells operated by the operator within 300 feet of the well to be fracture stimulated.</p> <p>3. Bradenhead pressure gauges are to be installed 24 hours prior to stimulation. The gauges are to read at least once during every 24-hour period until 24-hours after stimulation is completed (post flowback). The gauges are to be of the type able to read current pressure and record the maximum encountered pressure in a 24-hour period. The gauge is to be reset between each 24-hour period. The pressures are to be recorded and saved. Alternate electronic measurement may be used to record the prescribed pressures.</p> <p>4. If at any time during stimulation or the 24-hour post-stimulation period, the bradenhead annulus pressure of the treatment well or offset wells increases more than 200 psig, as per Rule 341, the operator of the well being stimulated shall verbally notify the Director as soon as practicable, but no later than twenty-four (24) hours following the incident. Within fifteen (15) days after the occurrence, the operator shall submit a Sundry Notice, Form 4, giving all details, including corrective actions taken.</p>
Drilling/Completion Operations	<p>"Prior to drilling operations, Operator may perform an anti-collision review of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision review may include MWD or gyro surveys and surface locations of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well may only be drilled if the anti-collision review results indicate that the risk of collision is sufficiently low as defined by the anti-collision plan, with separation factors greater than 1.5, or if the risk of collision has been mitigated through other means including shutting in wells, plugging wells, increased drilling fluid in the event of lost returns or as is appropriate for the specific situation. In the event of an increased risk of collision, that risk will be mitigated to prevent harm to people, the environment or property. For the proposed well, upon conclusion of drilling operations, an as-constructed directional survey will be submitted to COGCC with the Form 5."</p> <p>At the time of permitting; the operator has identified the following well(s) as being within close proximity of the proposed well:</p> <p>NILES 29C-28HZ: - MILLER 22-28 - MILLER 13-28 - NILES S MILLER UNIT 2</p>

Total: 2 comment(s)