



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7289 • FAX (970) 353-7712

OUR INVOICE

600285

Date	12-23-11	Well Owner	Kerr McGee	Well No.	41-12	Lease	MORTON
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME-11)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		FL	890		
Surface	8 5/8" CSG-24#	Bottom of Surface		FL	880		
Plug		Plug Landed @	836	FL	Time On	0200	
Production		Pipe Landed @	880	FL	Plug Down	0515	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	560	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	186	Miles		
Fuel Surcharge	186	MILES		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	0423-0428	
Disp. Rate	5 BPM	Mixing	0428-0501	
Slurry Vol.	1.32 ³ Cu. Ft./Sk	Change Valves	0501-0504	
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0504-0515	
Water/Cement	6.25 Gal/SK		WBS/WO/CC	2028568
Water Temp.	60°F		G/L Acct.	80012090 Del
Total Slurry Vol.	131.6	BBLS Cement		
Landed Plug @	380	PSI/Final Lift @ 360	PSI	
Pre-Flush W/	20	BBLS H ₂ O	Tax Reference Code	Sub Total
Displace W/	53.1	BBLS H ₂ O	State CO 2.9%	Tax
Circulate	6	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		62			
1214/1218		Bulk Truck		62/62			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH, EVAN, ERNIE

Received By

Customer or His Agent