

Well

Operator
Location
API
County
State
Field
Footages

State Peterson 41-20

EnCana Oil & Gas (USA) Inc.
NE NE Section 20-T5N-R63W
05-123-22535
Weld
Colorado
Wattenberg
451' FNL & 477' FEL

Spud Date: 04-19-2006

TD Date: 04-27-2006

Log Tops

Parkman	3450'
Sussex	4140'
Sharon Spgs.	6422'
Niobrara	6460'
Codell	6620'
J Sand	7070'
Dakota	7324'
Log TD	7468'

CIBP

Set @ 6670' on 01-05-12

CFP

Set @ 6530' on 01-05-12
Drilled out 01-23-12

CBP

Set CBP @ 6315' on 05-09-06
Drilled out on 05-10-06

CFP

Set @ 6573' on 05-05-06
Drilled out on 05-10-06

CFP

Set @ 6576' on 05-04-06
Drilled out on 05-10-06

CBP

Set @ 6750' on 05-04-06
Drilled out on 05-10-06

Production Tubing

2-3/8" tubing, set @ 6599'
on 01-23-12

Surface Casing and Cement

8 5/8", 24#, landed @ 408', cemented with 285 sxs

Main Hole

7-7/8" to TD

Production Casing and Cement

4-1/2", 11.6#, landed @ 7460.50', cemented with 260 sxs

DV Tool

Set @ 3967', cemented above DV tool with 300 sxs

Niobrara Refrac

Frac'd 6464' - 6486' with 138,282 gal frac fluid and 250,010# sand. 01-05-12

Codell Refrac

Frac'd 6615' - 6632' with 119,327 gal frac fluid and 250,010# sand. 01-05-12

Niobrara

Perf'd Niobrara "A" from 6464' - 6486' @ 4 spf, 44 holes
Perf'd Niobrara "B" from 6547' - 6567' @ 4 spf, 40 holes
Frac'd with 167,560 gal frac fluid and 250,200# sand.
05-05-06

Codell

Perf'd Codell from 6620' - 6632' @ 4 spf, 48 holes
Re-run Perf from 6615' - 6627' @ 2 spf, 24 holes
Frac'd with 111,556 gal frac fluid and 250,100# sand.
05-04-06

Perf'd J Sand from 7074' - 7136' @ 2 spf 84 holes
Frac'd J Sand with 160,051 gal frac fluid and 253,149# sand.
05-04-06

7470' — Driller's
TD

