

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400224220

Date Received:

04/05/2012

PluggingBond SuretyID

20110027

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☐ COALBED ☐ OTHER CO2  
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: KINDER MORGAN CO2 CO LP

4. COGCC Operator Number: 46685

5. Address: 17801 HWY 491

City: CORTEZ State: CO Zip: 81321

6. Contact Name: Paul Belanger Phone: (970)882-2464 Fax: (970)882-5521

Email: Paul\_Belanger@kindermorgan.com

7. Well Name: YA Well Number: 7

8. Unit Name (if appl): MCELMO DOME Unit Number: 047653X

9. Proposed Total Measured Depth: 8275

WELL LOCATION INFORMATION

10. QtrQtr: SWSE Sec: 13 Twp: 37N Rng: 18W Meridian: N

Latitude: 37.458440 Longitude: -108.782420

Footage at Surface: 615 feet FNL/FSL 2468 feet FEL/FWL FEL

11. Field Name: MCELMO Field Number: 53674

12. Ground Elevation: 6692 13. County: MONTEZUMA

14. GPS Data:

Date of Measurement: 03/19/2012 PDOP Reading: 1.5 Instrument Operator's Name: R J CAFFEY

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_ Bottom Hole: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_

Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_ Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 3753 ft

18. Distance to nearest property line: 167 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1320 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Leadville	LDVLL			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20080051

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

LEASE ATTACHED INCLUDES SWSE QTRQTR OF SECTION 13

25. Distance to Nearest Mineral Lease Line: 173 ft

26. Total Acres in Lease: 160

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☒ Yes ☐ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☒ Yes ☐ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☒ Yes ☐ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: de-water/cover:salt disp. fclt

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	20		0	80	100	80	0
SURF	12+1/4	9+5/8	36	0	2,925	1,100	2,925	0
1ST	8+3/4	7	29&32	0	7,900	1,770	7,900	0
OPEN HOLE	6			7900				7,900

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments This is the APD application for the vertical pilot hole as explained in the drilling plan; after production casing is set it will be drilled OH, logged and plugged back to a KOP for the horizontal well bore portion of the well. Form 15 pit permit is being submitted for 2 pits: pit 1 for most of the cuttings will be left on-site, de-watered and covered; Salt section cuttings and muds in vertical pilot will be de-watered and solids hauled offsite to disposal facility.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Paul E. Belanger

Title: Regulatory Contractor Date: 4/5/2012 Email: Paul\_Belanger@KinderMorgan.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### Attachment Check List

Att Doc Num	Name
400224220	FORM 2 SUBMITTED
400247941	OTHER
400257219	H2S CONTINGENCY PLAN
400268384	WELL LOCATION PLAT
400268504	LEGAL/LEASE DESCRIPTION
400268544	DRILLING PLAN

Total Attach: 6 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

### BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)