

FORM
5

Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400269878

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☐ Final completion ☒ Preliminary completion

1. OGCC Operator Number: 66571

4. Contact Name: Joan Proulx

2. Name of Operator: OXY USA WTP LP

Phone: (970) 263-3641

3. Address: P O BOX 27757

Fax: (970) 263-3694

City: HOUSTON State: TX Zip: 77227

5. API Number 05-045-20710-00

6. County: GARFIELD

7. Well Name: Cascade Creek

Well Number: 697-09-04B

8. Location: QtrQtr: NWSW Section: 4 Township: 6S Range: 97W Meridian: 6

Footage at surface: Distance: 1480 feet Direction: FSL Distance: 1120 feet Direction: FWL

As Drilled Latitude: As Drilled Longitude:

GPS Data:

Data of Measurement: PDOP Reading: GPS Instrument Operator's Name:

** If directional footage at Top of Prod. Zone Dist.: 593 feet. Direction: FNL Dist.: 2572 feet. Direction: FWL

Sec: 9 Twp: 6S Rng: 97W

** If directional footage at Bottom Hole Dist.: 626 feet. Direction: FNL Dist.: 2523 feet. Direction: FWL

Sec: 9 Twp: 6S Rng: 97W

9. Field Name: GRAND VALLEY

10. Field Number: 31290

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 12/18/2011 13. Date TD: 02/09/2012 14. Date Casing Set or D&A: 02/10/2012

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 9842 TVD** 9297 17 Plug Back Total Depth MD 9786 TVD** 9241

18. Elevations GR 8631 KB 8663

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL/CBL-VDL/GR-CCL
RST/Sigma Mode/GR-CCL
RST/Inelastic Capture/GR-CCL
CBL

20. Casing, Liner and Cement:

CASING

| Casing Type | Size of Hole | Size of Casing | Wt/Ft | Csg/Liner Top | Setting Depth | Sacks Cmt | Cmt Top | Cmt Bot | Status |
|-------------|--------------|----------------|-------|---------------|---------------|-----------|---------|---------|--------|
| CONDUCTOR | 20+0/0 | 16+0/0 | 65 | 0 | 85 | 4 | 0 | 85 | CALC |
| SURF | 14+3/4 | 9+5/8 | 36 | 0 | 2,665 | 1,204 | 0 | 2,665 | CALC |
| 1ST | 8+3/4 | 4+1/2 | 11.6 | 0 | 9,812 | 2,500 | | 9,812 | |

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: 12/20/2011

| Method used | String | Cementing tool setting/pref depth | Cement volume | Cement top | Cement bottom |
|-------------|--------|-----------------------------------|---------------|------------|---------------|
| | SURF | | 100 | 0 | 2,665 |
| | 1ST | | 227 | | 9,812 |

Details of work:

A Form 4 Sundry Notice for a variance to Rule 317.h. was approved by D. Andrews on 3/22/12 for the surface casing cementing.

The production casing was recemented from 1000' down to surface through the back side on 3/12/12; PJR attached.

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

| FORMATION NAME | Measured Depth | | Check if applies | | COMMENTS (All DST and Core Analyses must be submitted to COGCC) |
|----------------|----------------|--------|--------------------------|--------------------------|---|
| | Top | Bottom | DST | Cored | |
| | | | <input type="checkbox"/> | <input type="checkbox"/> | |

Comment:

Preliminary Form 5.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Joan Proulx

Title: Regulatory Analyst Date: _____ Email: joan_proulx@oxy.com

Attachment Check List

| Att Doc Num | Document Name | attached ? | | | |
|-----------------------------|-----------------------|------------|-------------------------------------|----|-------------------------------------|
| <u>Attachment Checklist</u> | | | | | |
| 400269886 | CMT Summary * | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
| | Core Analysis | Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
| 400269884 | Directional Survey ** | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
| | DST Analysis | Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
| | Logs | Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
| | Other | Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
| <u>Other Attachments</u> | | | | | |
| 400269888 | DIRECTIONAL DATA | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |

General Comments

| User Group | Comment | Comment Date |
|------------|---------|--------------|
| | | |

Total: 0 comment(s)