



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600280

Date <u>1/4/2012</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>3-12</u>	Lease <u>Morton</u>				
County <u>WELD</u>	State <u>Colorado</u>						
Charge to <u>Kerr McGee Oil &amp; Gas Onshore, LP</u>							
Address <u>1999 Broadway, Suite 3700</u> <u>(XTREME # 11)</u>							
City, State Zip <u>Denver, Colorado 80202</u>							
Type of Job	Depth	Ft. <u>877</u>					
Surface <u>8 5/8" CSG 24"</u>	Bottom of Surface	Ft. <u>867</u>					
Plug	Plug Landed @ <u>825' AFT</u>	Time On <u>2000</u>					
Production	Pipe Landed @ <u>867' AFT</u>	Plug Down <u>2200</u>					
Description	Qty.	Meas.	Unit Price				
Set Up Charge	1						
Cement Neat <u>TYPE III</u>	550	SKS					
Poz. Mix							
Calcium Chloride	2.5	%					
Gel % Flo-Crete 1/4 # Per Sack	<u>2046301 ORL</u>						
Mileage Charge	<u>80012090</u>	199	Miles				
Fuel Surcharge		199	MILES				
Additional Cement			SKS				
Mixing Rate	4 BPM	Pre-Flush	1911, 1915				
Disp. Rate	5 BPM	Mixing	1915, 1947				
Slurry Vol.	1.32 Cu. Ft./Sk	Change Valves	1947, 1950				
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1950, 2200				
Water/Cement	6.25 Gal/SK						
Water Temp.	<u>47</u>						
Total Slurry Vol.	<u>129.3</u>	BBLS Cement					
Landed Plug @	<u>350</u>	PSI/Final Lift @ <u>270</u>	PSI				
Pre-Flush W/ <u>20</u>	BBLS H <sub>2</sub> O	Tax Reference Code	Sub. Total				
Displace W/ <u>52.4</u>	BBLS H <sub>2</sub> O	State <u>CO 2.9%</u>	Tax				
Circulate <u>5</u>	BBLS Cement		Total				
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1201</u>		Pump Truck		<u>666</u>			
<u>1216/1234</u>		Bulk Truck		<u>666/666</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim/Adam/Jason

Received By Tom Bowel  
Customer or His Agent