

FORM

2

Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400239270

Date Received:

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
 SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refiling ☐Sidetrack ☐

PluggingBond SuretyID

20030009

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: MARI CLARK Phone: (303)228-4413 Fax: (303)228-4286

Email: mclark@nobleenergyinc.com

7. Well Name: GUTTERSEN D

Well Number: 30-68-1HN

8. Unit Name (if appl):

Unit Number:

9. Proposed Total Measured Depth: 11225

## WELL LOCATION INFORMATION

10. QtrQtr: NWNW Sec: 29 Twp: 3N Rng: 64W Meridian: 6

Latitude: 40.199940

Longitude: -104.583220

Footage at Surface: 1298 feet FNL/FSL FNL 370 feet FEL/FWL FWL

11. Field Name: WATTENBERG

Field Number: 90750

12. Ground Elevation: 4787

13. County: WELD

14. GPS Data:

Date of Measurement: 10/28/2011 PDOP Reading: 2.5 Instrument Operator's Name: DAVID C HOLMES

15. If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FNL 989 FNL 532 FEL 990 FNL 535 FWL  
 Sec: 30 Twp: 3N Rng: 64W Sec: 30 Twp: 3N Rng: 64W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 2590 ft

18. Distance to nearest property line: 370 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 115 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	407-87	320	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

N/2, N/2SE OF SECTION 30, T3N, R64W

25. Distance to Nearest Mineral Lease Line: 535 ft

26. Total Acres in Lease: 400

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	18+1/2	16+0/0		0	100	6	100	0
SURF	13+3/4	9+5/8	36	0	750	372	750	0
1ST	8+3/4	7+0/0	26	0	7,204	504	7,204	
1ST LINER	6+1/8	4+1/2	11.6	7050	11,225			

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments 1ST STRING TOP OF CEMENT = 200' ABOVE NIOBRARA. THE PRODUCTION LINER WILL BE HUNG OFF INSIDE 7" CASING. UNIT CONFIGURATION =N/2 OF SECTION 30. NOBLE ENERGY INC. CERTIFIES THAT THE LEASES SHALL BE COMMITTED TO THE UNIT. WELL IS TO BE TWINNED WITH PROPOSED GUTTERSEN D29-30D, D29-67HN, 29-69HN, 30-69-1HN CREATING A 5 WELL PAD. NOBLE ACKNOWLEDGES THAT THE ADAMS D30-27D IS LESS THAN THE MINIMUM ALLOWED INTRAWELL DISTANCE & HAVE PROVIDED A BMP TO ADDRESSES IT. EXCEPTION LOCATION TO RULE 318A.a and 318A.c REQUESTED AND ATTACHED.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: MARI CLARK

Title: REG. ANALYST II Date: \_\_\_\_\_ Email: mclark@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### Attachment Check List

Att Doc Num	Name
400247679	DIRECTIONAL DATA
400269772	30 DAY NOTICE LETTER
400269774	DEVIATED DRILLING PLAN
400269775	EXCEPTION LOC REQUEST
400269776	EXCEPTION LOC WAIVERS
400269777	WELL LOCATION PLAT
400269778	PROPOSED SPACING UNIT
400269790	EXCEPTION LOC REQUEST
400269799	SURFACE AGRMT/SURETY

Total Attach: 9 Files

### General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)

### BMP

Type	Comment
Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public and Environment (CDPHE) General Permit No. COR-038637. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location, and will remain in place until the pad reaches final reclamation.
General Housekeeping	Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pickup trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.
Material Handling and Spill Prevention	Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR 112.

Total: 3 comment(s)