



**CEMENTER'S WELL SERVICE, INC.**  
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

**600311**

Date <u>1/26/12</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>38C-26H2</u>	Lease <u>Camp</u>
County <u>weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil &amp; Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (MAJOR #42)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Ft. <u>937</u>	
(Surface) <u>9 5/8" CSG-30" 12 1/4" Hole</u>	Bottom of Surface	Ft. <u>927</u>	
Plug	Plug Landed @ <u>883</u>	Ft.	Time On <u>1700</u>
Production	Pipe Landed @ <u>927</u>	Ft.	Plug Down <u>2230</u>

Description	Qty.	Meas.
Set Up Charge	1	
Cement Neat <u>Type BT Duaine Bell</u>	<u>440</u>	SKS
Poz. Mix		
Calcium Chloride <u>User ID ZDSB4</u>	2.5	%
Gel % <u>Fio-Cete 1A</u>		
<u>WBS/WO/CC 2054250</u>		
Mileage Charge <u>G/L Acct. 80012090</u>	<u>132</u>	Miles
Fuel Surcharge	<u>132</u>	Miles
Additional Cement		SKS
Mixing Rate <u>4 BPM</u>	Pre-Flush <u>2148-</u>	<u>2154</u>
Disp. Rate <u>5 BPM</u>	Mixing <u>2154-</u>	<u>2213</u>
Slurry Vol. <u>1.32<sup>3</sup> Cu.Ft./Sk</u>	Change Valves <u>2213-</u>	<u>2216</u>
Slurry Wt. <u>14.8 - 15.0 PPG</u>	Displacement <u>2216-</u>	<u>2230</u>
Water/Cement <u>6.25 Gal/SK</u>		
Water Temp. <u>51°F</u>		
Total Slurry Vol. <u>103.4</u>	BBLS Cement	
Landed Plug @ <u>500</u>	PSI/Final Lift @ <u>250</u>	PSI
Pre-Flush W/ <u>30</u>	BBLS H <sub>2</sub> O	Tax Reference Code
Displace W/ <u>68.2</u>	BBLS H <sub>2</sub> O	State <u>CO 2.9%</u>
Circulate <u>5</u>	BBLS Cement	
		Sub Total
		Tax
		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyom.
<u>1208</u>		Pump Truck		<u>44</u>	
<u>1214/1216</u>		Bulk Truck		<u>44/44</u>	

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Steve & Evan

Received By

Randy Case  
Customer or His Agent