

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400264428

Date Received:

03/23/2012

PluggingBond SuretyID

20080107

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
 SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐Sidetrack ☐3. Name of Operator: QUICKSILVER RESOURCES INC4. COGCC Operator Number: 102555. Address: 801 CHERRY ST - #3700 UNIT 19City: FT WORTH State: TX Zip: 761026. Contact Name: Pamela Osburn Phone: (817)665-4918 Fax: (817)665-5009Email: posburn@qrinc.com7. Well Name: SIMOES Well Number: 31-30

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8500

WELL LOCATION INFORMATION

10. QtrQtr: LOT 6 Sec: 30 Twp: 6N Rng: 90W Meridian: 6Latitude: 40.453600 Longitude: -107.531933

Footage at Surface: 895 feet FNL 2057 feet FEL
 FNL/FSL FEL/FWL

11. Field Name: WILDCAT Field Number: 9999912. Ground Elevation: 6622 13. County: MOFFAT

14. GPS Data:

Date of Measurement: 02/29/2012 PDOP Reading: 1.2 Instrument Operator's Name: UINTAH ENGINEERING15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 305 ft18. Distance to nearest property line: 437 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 2100 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

SEE ATTACHED MINERAL LEASES

25. Distance to Nearest Mineral Lease Line: 600 ft

26. Total Acres in Lease: 245

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☒ Yes ☐ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	20	16		0	20			
SURF	12+1/4	9+5/8	36	0	1,200	395	1,200	0
1ST	8+3/4	7	26	0	6,600	630	6,600	1,000
2ND	6+1/8	4+1/2	11.6	0	8,420	320	8,420	3,650

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments SURFACE USE AGREEMENT OBTAINED. MEMORANDUM ATTACHED

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Pamela S. Osburn

Title: Sr. Regulatory Analyst

Date: 3/23/2012

Email: posburn@qrinc.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: 4/19/2012

API NUMBER

05 081 07723 00

Permit Number: _____ Expiration Date: 4/18/2014

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Before placing oil/salt based muds in a pit, operator must file and receive prior approval of a Pit Permit, Form 15. COGCC regulations regarding pit permits can be found in Rule 903.a.(3). PIT PERMITTING/REPORTING REQUIREMENTS.

(1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

(2) CEMENT ON PRODUCTION CASING MUST BE AT LEAST 200' ABOVE TOP OF FT. UNION AND COMPLY WITH RULES 209 AND 317.I. SEGREGATE OIL, GAS, AND FRESH-WATER-BEARING ZONES AND PROTECT COAL SEAMS. VERIFY TOP WITH CBL.

(3) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 540 FEET DEEP.

Attachment Check List

Att Doc Num	Name
400264428	FORM 2 SUBMITTED
400264514	WELL LOCATION PLAT
400264516	SURFACE AGRMT/SURETY
400264520	LEGAL/LEASE DESCRIPTION
400264521	LEGAL/LEASE DESCRIPTION
400264522	LEGAL/LEASE DESCRIPTION

Total Attach: 6 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	LGD & pub. comments waived. Final Review--passed.	4/17/2012 1:14:01 PM
Permit	note that location is on BLM coal-only lease.	4/10/2012 7:58:19 AM

Total: 2 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)