

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400274604

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 69175

4. Contact Name: Jeff Glossa

2. Name of Operator: PETROLEUM DEVELOPMENT CORPORATION

Phone: (303) 831-3972

3. Address: 1775 SHERMAN STREET - STE 3000

Fax: (303) 860-5838

City: DENVER State: CO Zip: 80203

5. API Number 05-123-33262-00

6. County: WELD

7. Well Name: Zeiler

Well Number: 14-7DU

8. Location: QtrQtr: SWSW Section: 7 Township: 5N Range: 67W Meridian: 6

Footage at surface: Distance: 1061 feet Direction: FSL Distance: 925 feet Direction: FWL

As Drilled Latitude: 40.409860 As Drilled Longitude: -104.941190

GPS Data:

Date of Measurement: 03/29/2012 PDOP Reading: 1.3 GPS Instrument Operator's Name: Holly L. Tracy

** If directional footage at Top of Prod. Zone Dist.: 665 feet. Direction: FSL Dist.: 603 feet. Direction: FWL

Sec: 7 Twp: 5N Rng: 67W

** If directional footage at Bottom Hole Dist.: 664 feet. Direction: FSL Dist.: 595 feet. Direction: FWL

Sec: 7 Twp: 5N Rng: 67W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 11/17/2011 13. Date TD: 11/21/2011 14. Date Casing Set or D&A: 11/22/2011

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7890 TVD** 7845 17 Plug Back Total Depth MD 7450 TVD** 7405

18. Elevations GR 4950 KB 4974

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL, CNL/CDL/DIL

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24	0	416	300	0	416	VISU
1ST	7+7/8	4+1/2	11.6	0	7,862	905	0	7,862	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____					
Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
Details of work:					

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES					
FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	3,515		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,145		<input type="checkbox"/>	<input type="checkbox"/>	
SHANNON	4,602		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	6,945		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,244		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,264		<input type="checkbox"/>	<input type="checkbox"/>	
GREENHORN	7,324		<input type="checkbox"/>	<input type="checkbox"/>	
GRANEROS	7,542		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	7,728		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Jeff Glossa

Title: Sr Engineering Tech Date: _____ Email: jglossa@petd.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400274624	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Directional Survey **	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400274625	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400274621	LAS-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400274622	LAS-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400274623	IND-DENS-NEU	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400274626	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)