



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600356

Date	2/7/2012	Well Owner	Kerr McGee	Well No.	28-2	Lease	DARCO
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME#15)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Ft.	961		
Surface	8 5/8" CSG 24"	Bottom of Surface		Ft.	951		
Plug		Plug Landed @	906	Ft.	Time On	2015	
Production		Pipe Landed @	951	Ft.	Plug Down	0000	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	600	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	246	Miles		
Fuel Surcharge	246	MI/MS		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush 2304	2310		
Disp. Rate 5 BPM	Mixing 2310	2345		
Slurry Vol. 1.32 ³ Cu.Ft./Sk	Change Valves 2345	2349		
Slurry Wt. 14.8 - 15.0 PPG	Displacement 2349	0000		
Water/Cement 6.25 Gal/SK				
Water Temp. 51				
Total Slurry Vol. 141.0	BBLS Cement			
Landed Plug @ 475	PSI/Final Lift @ 170	PSI		
Pre-Flush W/ 30	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ 57.6	BBLS H ₂ O	State CO 2.9%	Tax	
Circulate 6	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		82			
1216		Bulk Truck		82/82			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to change without notice.

Delivered By JSM/ADAM JASON

Received By Keith R. Salen
Customer or His Agent