



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600347

Date	2-12-12	Well Owner	Kerr McGee	Well No.	89-2	Lease	DALOWO
County		State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME #15)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	955		
Surface	8 5/8" CSG-24#	Bottom of Surface		Fl.	945		
Plug		Plug Landed @	900	Fl.	Time On	1030	
Production		Pipe Landed @	945	Fl.	Plug Down	1330	

Description	Qty.	Mess.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	600	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge	246	Miles		
Fuel Surcharge	246	MILES		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	1231	1239
Disp. Rate	5 BPM	Mixing	1239	1315
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves	1315	1318
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1318	1330
Water/Cement	6.25 Gal/SK			
Water Temp.	56°F			
Total Slurry Vol.	141.0	BBLS Cement		
Landed Plug @	300	PSI/Final Lift @	280	PSI
Pre-Flush Wt	30	BBLS H ₂ O	Tax Reference Code	Sub Total
Displace Wt	57.2	BBLS H ₂ O	State CO 2.9%	Tax
Circulate	5	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		82			
1210/1218		Bulk Truck		82/82			

2049223.DRL

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH, ERNIE

Received By

Keith R. Nolen
Customer or His Agent