

**FORM
5**Rev
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:
400275439

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 96850	4. Contact Name: Julie Lawson
2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC	Phone: (303) 260-4533
3. Address: 1001 17TH STREET - SUITE #1200	Fax: (303) 629-8268
City: DENVER State: CO Zip: 80202	

5. API Number 05-045-20162-00	6. County: GARFIELD
7. Well Name: T & T and Assoc. LTD	Well Number: PA 512-7
8. Location: QtrQtr: LOT2 Section: 7 Township: 7S Range: 95W Meridian: 6	
Footage at surface: Distance: 1213 feet Direction: FNL	Distance: 1500 feet Direction: FWL
As Drilled Latitude: 39.456450	As Drilled Longitude: -108.043853

GPS Data:

Data of Measurement: 03/30/2011 PDOP Reading: 1.4 GPS Instrument Operator's Name: J. Kirkpatrick

** If directional footage at Top of Prod. Zone Dist.: 2330 feet. Direction: FNL Dist.: 311 feet. Direction: FWL

Sec: 7 Twp: 7S Rng: 95W

** If directional footage at Bottom Hole Dist.: 2328 feet. Direction: FNL Dist.: 308 feet. Direction: FWL

Sec: 7 Twp: 7S Rng: 95W

9. Field Name: PARACHUTE 10. Field Number: 67350

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 08/28/2011 13. Date TD: 09/02/2011 14. Date Casing Set or D&A: 09/03/2011

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 6660 TVD** 6258 17 Plug Back Total Depth MD 6612 TVD** 6210

18. Elevations GR 5083 KB 5109

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

SP/GR/HDIL/ZDL/CN and CBL

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	18	48	0	84	31	0	84	VISU
SURF	13+1/2	9+5/8	32.3	0	1,164	320	0	1,164	VISU
1ST	7+7/8	4+1/2	11.6	0	6,620	990	2,780	6,620	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH	1,302		<input type="checkbox"/>	<input type="checkbox"/>	
MESAVERDE	3,568		<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	6,036		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	6,544		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

Please note: the "as-drilled" GPS information provided is actual data of the existing well conductor location prior to the big rig spud date.

Surface Casing = 1

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Julie Lawson

Title: Permit Tech II

Date:

Email: julie.lawson@wpenergy.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400275449	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400275447	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400275452	Other	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
<u>Other Attachments</u>					
400275451	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General CommentsUser GroupCommentComment Date

--	--	--

Total: 0 comment(s)