

FORM  
2

Rev  
12/05

# State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400276665

Date Received:

## APPLICATION FOR PERMIT TO:

1.  Drill,  Deepen,  Re-enter,  Recomplete and Operate

### 2. TYPE OF WELL

OIL  GAS  COALBED  OTHER \_\_\_\_\_  
SINGLE ZONE  MULTIPLE  COMMINGLE

Refiling

Sidetrack

PluggingBond SuretyID

20070074

3. Name of Operator: LARAMIE ENERGY II, LLC

4. COGCC Operator Number: 10232

5. Address: 1512 LARIMER ST STE 1000

City: DENVER State: CO Zip: 80202

6. Contact Name: Wayne P Bankert Phone: (970)812-5310 Fax: (303)339-4399

Email: wbankert@laramie-energy.com

7. Well Name: Beaver Creek Ranch Well Number: 08-13D

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 9973

## WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 8 Twp: 7S Rng: 93W Meridian: 6

Latitude: 39.454734 Longitude: -107.805187

Footage at Surface: 697 feet FNL/FSL 403 feet FEL/FWL FWL

11. Field Name: WILDCAT Field Number: 99999

12. Ground Elevation: 7833 13. County: GARFIELD

### 14. GPS Data:

Date of Measurement: 04/22/2009 PDOP Reading: 1.5 Instrument Operator's Name: George allen

15. If well is  Directional  Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 164 FSL 646 FWL \_\_\_\_\_ Bottom Hole: FNL/FSL 164 FNL 646 FWL \_\_\_\_\_  
Sec: 8 Twp: 7S Rng: 93W Sec: 8 Twp: 7S Rng: 93W

16. Is location in a high density area? (Rule 603b)?  Yes  No

17. Distance to the nearest building, public road, above ground utility or railroad: 7656 ft

18. Distance to nearest property line: 612 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1400 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	139-76		

21. Mineral Ownership:  Fee  State  Federal  Indian Lease #: \_\_\_\_\_

22. Surface Ownership:  Fee  State  Federal  Indian

23. Is the Surface Owner also the Mineral Owner?  Yes  No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease?  Yes  No

23b. If 23 is No:  Surface Owners Agreement Attached or  \$25,000 Blanket Surface Bond  \$2,000 Surface Bond  \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

SEC. 8 S2SW; SEC. 18 L1, NENW,N2NE, SWNE; TWN 7S RNG. 93W 6TH PM

25. Distance to Nearest Mineral Lease Line: 164 ft 26. Total Acres in Lease: 280

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated?  Yes  No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling?  Yes  No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling?  Yes  No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)?  Yes  No

31. Mud disposal:  Offsite  Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method:  Land Farming  Land Spreading  Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26+0/0	16+0/0	42.0	0	40	78	40	0
SURF	14+3/4	8+5/8	32.0	0	1,500	900	1,500	0
1ST	7+7/8	4+1/2	11.6	0	9,973	1,100	9,973	7,265

32. BOP Equipment Type:  Annular Preventer  Double Ram  Rotating Head  None

33. Comments DRILLING WILL INNCORPORATE A CLOSED MUD SYSTEM WITH CUTTINGS TRENCH. NO VISIBLE IMPROVEMENTS WITHIN 200' OF WELLHEAD.

34. Location ID: 414294

35. Is this application in a Comprehensive Drilling Plan ?  Yes  No

36. Is this application part of submitted Oil and Gas Location Assessment ?  Yes  No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Wayne P. Bankert

Title: Snr. Reg. & Env. Coord. Date: \_\_\_\_\_ Email: wbankert@laramie-energy.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

**API NUMBER**

05 045 18821 00

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

**CONDITIONS OF APPROVAL, IF ANY:**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

\_\_\_\_\_

### Attachment Check List

Att Doc Num	Name
400276670	SURFACE AGRMT/SURETY

Total Attach: 1 Files

#### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

#### BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)