

CHESAPEAKE OPERATING, INC.

P. O. Box 18496
 OKLAHOMA CITY, OKLAHOMA 73154-0496
 405/848-8000
 405/879-9573 FAX

Daily Activity Operated Report

WRD FEDERAL 5-29		29-2N-97W		White River Dome
Well #: 253413		AFE: 300278	RIO BLANCO, CO	Wasatch 2,700'
		Cost	WI: 98.000000	NRI: 81.830000
Date	Day	Footage	Cum Cost	Present Operation
12/03/01		0'	\$8,808	Perforate Wasatch 351' to 496'
		0'	\$11,198	MIRU well service, pull tbg, perforate Wasatch 351' - 356', 386' - 394', 483' - 496', blow on csg, RIH w/ tbg, SDFN. Perforate Wasatch 351' - 356', 386' - 394', 483' - 496'
12/04/01		0'	\$11,120	RIH w/ pump & rods
		0'	\$22,318	RIH w/ 76 jts 2 3/8" tbg, 1 - 10' MA, 1 - 1.10 SN, land @ 2,387', 94 - 5/8" rods, 1 - 2', 1 - 4', 5/8" rod subs, 1 - 1/14" x 12' polish rod, 1 - 1/14" x 1 3/8" x 6' liner, RDMO, SDFN.
12/05/01		0'	\$2,600	Dig ditch from WH to pit, plumb in WH, wrap flowline, backfill ditch
		0'	\$24,918	
12/06/01		0'	\$1,800	Set pumping unit, work on gas line & water line, build pad
		0'	\$26,718	
12/07/01		0'	\$1,100	Finish hooking up gas line to motor
		0'	\$27,818	Build fence around pumping unit, finish hooking up gas line to motor, put well on line, CP 45#, pumping water, SDFN.

12/07/01 4:24:02PM