



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

200178

(P.O.# 164433)

Date 9-28-11	Well Owner SYNERGY RESOURCES	Well No. 42-36D	Lease HAYTHORN
County WELD	State COLORADO	Field	
Charge to ENSIGN US DRILLING	Charge Code		
Address PO BOX 17805 (ENSIGN #33)	For Office Use Only		
City, State DENVER COLORADO 80217			
Pump Truck No. 1202	Code	Bulk Truck No. 1214	Code
Type of Job	Depth	Ft. 527	To
Surface 8 5/8" CSG-24#	Bottom of Surface	Ft. 517	To
Plug	Plug Landed @ 475	Ft.	Time On 0830
Production	Pipe Landed @ 517	Ft.	Time Off PLUG DOWN 1100

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Neat ✓	370	SKS		
	Poz. Mix				
	Calcium Chloride	3%			
	Gel % Flo-Cele 1/4# Per Sack				
	Handling Charge				
	Hauling Charge				
	Additional Cement	40	SKS	14.85	
8 5/8"	CENTRALIZERS	3		70.00	
"	CEMENT BASKET	1			
"	GUIDE SHOE	1			
"	BAFFLE PLATE	1			
	BOX THREADLOCK	1			
	MIX RATE 4 BPM	SLURRY VOL 1.18	FT ³ /SK	WATER TEMP	
	DISP RATE 5 BPM	SLURRY WT 15.2	PPG		
	PLUG LANDED @ PSI	TOTAL SLURRY VOL 86.1	BBL CEMENT		
Remarks: PREFLUSH W/20 BBL H2O	Tax Reference Code	Sub Total			
DISPLACE W/30.2 BBL H2O	State CO 2.9 %	Tax			
CIRCULATE 3 BBL CEMENT	Disc.	Total			

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other
1202		Pump Truck		24		
1214		Bulk Truck		24		

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **JOSH, JOE, EVAN, ERNIE**

Received By

Ron Black
Customer or His Agent