

FORM  
2

Rev  
12/05

# State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400221795

Date Received:

04/04/2012

PluggingBond SuretyID

20030009

## APPLICATION FOR PERMIT TO:

1.  Drill,  Deepen,  Re-enter,  Recomplete and Operate

### 2. TYPE OF WELL

OIL  GAS  COALBED  OTHER \_\_\_\_\_  
SINGLE ZONE  MULTIPLE  COMMINGLE

Refiling

Sidetrack

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: JAN KAJIWARA Phone: (303)228-4092 Fax: (303)228-4286

Email: jkajiwara@nobleenergyinc.com

7. Well Name: STROH PC O Well Number: 13-79HN

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 11509

## WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 13 Twp: 4N Rng: 67W Meridian: 6

Latitude: 40.305190 Longitude: -104.847650

Footage at Surface: 200 feet FSL 294 feet FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4846 13. County: WELD

### 14. GPS Data:

Date of Measurement: 05/10/2011 PDOP Reading: 1.2 Instrument Operator's Name: GREGORY A CLARK

15. If well is  Directional  Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_ Bottom Hole: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_  
729 FSL 73 FEL 535 FNL 75 FEL  
Sec: 14 Twp: 4N Rng: 67W Sec: 14 Twp: 4N Rng: 67W

16. Is location in a high density area? (Rule 603b)?  Yes  No

17. Distance to the nearest building, public road, above ground utility or railroad: 249 ft

18. Distance to nearest property line: 200 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 550 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	407-87	320	GWA

21. Mineral Ownership:  Fee  State  Federal  Indian Lease #: \_\_\_\_\_

22. Surface Ownership:  Fee  State  Federal  Indian

23. Is the Surface Owner also the Mineral Owner?  Yes  No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease?  Yes  No

23b. If 23 is No:  Surface Owners Agreement Attached or  \$25,000 Blanket Surface Bond  \$2,000 Surface Bond  \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T4N-R67W SECT. 14: E/2, E/2SW/4

25. Distance to Nearest Mineral Lease Line: 535 ft 26. Total Acres in Lease: 400

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated?  Yes  No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling?  Yes  No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling?  Yes  No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)?  Yes  No

31. Mud disposal:  Offsite  Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method:  Land Farming  Land Spreading  Disposal Facility Other: CLOSED LOOP

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	18+1/2	16	0	0	100	6	100	0
SURF	13+3/4	9+5/8	36	0	700	348	700	0
1ST	8+3/4	7	26	0	7,482	523	7,482	
1ST LINER	6+1/8	4+1/2	11.6	7295	11,509			

32. BOP Equipment Type:  Annular Preventer  Double Ram  Rotating Head  None

33. Comments UNIT CONFIGURATION = SEC. 13: W/2W/2. SEC. 14: E/2E/2. FOUR SUAs IN THE ATTACHMENT.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ?  Yes  No

36. Is this application part of submitted Oil and Gas Location Assessment ?  Yes  No


I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: JAN KAJIWARA

Title: REGULATORY ANALYST Date: 4/4/2012 Email: jkajiwara@nobleenergyinc.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 4/26/2012

API NUMBER Permit Number: \_\_\_\_\_ Expiration Date: 4/25/2014

05 123 35465 00

CONDITIONS OF APPROVAL, IF ANY: \_\_\_\_\_

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Operator must meet water well testing requirements per Rule 318A.

- 1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU.
- 2) Comply with Rule 317.i and provide cement coverage from end of 7" production casing to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

### **Attachment Check List**

Att Doc Num	Name
1694912	VARIANCE REQUEST
1694913	PROPOSED BMPs
400221795	FORM 2 SUBMITTED
400221900	30 DAY NOTICE LETTER
400221903	WELL LOCATION PLAT
400221905	EXCEPTION LOC WAIVERS
400265668	DEVIATED DRILLING PLAN
400265670	DIRECTIONAL DATA
400268254	EXCEPTION LOC REQUEST
400268261	PROPOSED SPACING UNIT
400268262	SURFACE AGRMT/SURETY

Total Attach: 11 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	Final Review Completed. No LGD or public comment received.	4/26/2012 1:14:24 PM
Permit	Operator requests approval of a Rule 318Am exception location: Wellhead is to be located less than 150' from an existing wellbore. Request and waivers attached.	4/26/2012 1:13:21 PM
Permit	Changed "distance to nearest bldg, road, RR & utility" from 275' (RD) to 249' (OHP) per operator. Attached the Variance Request letter for 318A.m & the additional fracing BMP's. OK to pass 4/24/12.	4/11/2012 9:28:39 AM
Permit	Operator requests approval of a Rule 318Aa and Rule 318Ac exception location: Wellhead is to be located outside of a GWA drilling window and will be located more than 50' from an existing well location. Request and waivers attached.	4/9/2012 1:13:58 PM
Permit	ON HOLD: requesting to change "distance to nearest bldg, road, RR & utility" from 275' (RD) to 249' (OHP). Requesting the Variance letter for 318A.m & the addition of the fracing BMP's.	4/9/2012 11:51:07 AM

Total: 5 comment(s)

## BMP

<u>Type</u>	<u>Comment</u>
Drilling/Completion Operations	<p>During and Post Stimulation: 1. At least seven (7) days prior to fracture stimulation, the operator is to notify all operators of non-operated wells within 300 feet of the wellbore to be fracture stimulated of the anticipated stimulation date and the recommended best management practice to shut-in all wells within 300' of the stimulated wellbore completed in the same formation.</p> <p>2. The operator will monitor the bradenhead pressure of all wells within 300 feet of the well to be fracture stimulated.</p> <p>3. Bradenhead pressure gauges are to be installed 24 hours prior to stimulation. The gauges are to read at least once during every 24-hour period until 24-hours after stimulation is completed (post flowback). The gauges are to be of the type able to read current pressure and record the maximum encountered pressure in a 24-hour period. The gauge is to be reset between each 24-hour period. The pressures are to be recorded and saved. Alternate electronic measurement may be used to record the prescribed pressures. Data shall be kept for a period of one year.</p> <p>4. If at any time during stimulation or the 24-hour post-stimulation period, the bradenhead annulus pressure of the treatment well or offset wells increases more than 200 psig, as per Rule 341, the operator of the well being stimulated shall verbally notify the Director as soon as practicable, but no later than twenty-four (24) hours following the incident. Within fifteen (15) days after the occurrence, the operator shall submit a Sundry Notice, Form 4, giving all details, including corrective actions taken.</p>
Storm Water/Erosion Control	<p>Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil &amp; Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) General Permit No. COR-038637. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location, and will remain in place until the pad reaches final reclamation.</p>
General Housekeeping	<p>Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pickup trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.</p>
Final Reclamation	<p>Anti-collision: Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5.</p>
Material Handling and Spill Prevention	<p>Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil &amp; Gas operations throughout the state of Colorado in accordance with CFR 112.</p>

Total: 5 comment(s)