

Map Unit Description

Weld County, Colorado, Southern Part

72 Vona loamy sand, 0 to 3 percent slopes

Setting

Elevation: 4600 to 5200 feet
 Mean annual precipitation: 13 to 15 inches
 Mean annual air temperature: 48 to 55 degrees F
 Frost-free period: 130 to 160 days

Composition

Vona and similar soils: 85 percent
 Minor components: 15 percent

Description of Vona

Setting

Landform: Terraces, plains
 Down-slope shape: Linear
 Across-slope shape: Linear
 Parent material: Alluvium and/or eolian deposits

Properties and Qualities

Slope: 0 to 3 percent
 Drainage class: Well drained
 Capacity of the most limiting layer to transmit water (Ksat): High (1.98 to 6.00 in/hr)
 Frequency of flooding: None
 Frequency of ponding: None
 Calcium carbonate maximum: 15 percent
 Gypsum maximum: 0 percent
 Available water capacity: Moderate (about 6.5 inches)

Interpretive Groups

Land capability classification (irrigated): 3e
 Land capability (non irrigated): 4e
 Ecological site: Sandy Plains (R067BY024CO)

Typical Profile

0 to 6 inches: loamy sand
 6 to 28 inches: fine sandy loam
 28 to 60 inches: sandy loam

Minor Components

Remmit

Percent of map unit: 10 percent

Valent

Percent of map unit: 5 percent

T6N - R62W, 6th P.M.
SEC: 18, NWSW**Map Unit Description**

Weld County, Colorado, Southern Part

74 Vona loamy sand, 5 to 9 percent slopes

Setting

Elevation: 4600 to 5200 feet
 Mean annual precipitation: 13 to 15 inches
 Mean annual air temperature: 48 to 55 degrees F
 Frost-free period: 130 to 160 days

Composition

Vona and similar soils: 85 percent
 Minor components: 15 percent

Description of Vona**Setting**

Landform: Plains
 Down-slope shape: Linear
 Across-slope shape: Linear
 Parent material: Eolian deposits

Properties and Qualities

Slope: 5 to 9 percent
 Drainage class: Well drained
 Capacity of the most limiting layer to transmit water (Ksat): High (1.98 to 6.00 in/hr)
 Frequency of flooding: None
 Frequency of ponding: None
 Calcium carbonate maximum: 15 percent
 Gypsum maximum: 0 percent
 Available water capacity: Moderate (about 6.5 inches)

Interpretive Groups

Land capability classification (irrigated): 6e
 Land capability (non irrigated): 6e
 Ecological site: Sandy Plains (R067BY024CO)

Typical Profile

0 to 6 inches: loamy sand
 6 to 28 inches: fine sandy loam
 28 to 60 inches: sandy loam

Minor Components**Valent**

Percent of map unit: 10 percent

Remmit

Percent of map unit: 5 percent