

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400268412

Date Received:

04/04/2012

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refiling ☒

Sidetrack ☐

PluggingBond SuretyID

3. Name of Operator: BOPCO LP

4. COGCC Operator Number: 10172

5. Address: 10375 PARK MEADOW DR #450

City: LITTLETON State: CO Zip: 80124

6. Contact Name: Reed Haddock Phone: (303)305-7755 Fax: (303)799-5071

Email: rhaddock@basspet.com

7. Well Name: Yellow Creek Federal Well Number: 35-12-3533

8. Unit Name (if appl): Yellow Creek Unit Number: 68957

9. Proposed Total Measured Depth: 12200

WELL LOCATION INFORMATION

10. QtrQtr: SWNW Sec: 35 Twp: 1N Rng: 98W Meridian: 6

Latitude: 40.013840 Longitude: -108.365480

Footage at Surface: 1842 feet FNL/FSL 778 feet FEL/FWL  
FNL FWL

11. Field Name: Yellow Creek Field Number: 97955

12. Ground Elevation: 6339 13. County: RIO BLANCO

14. GPS Data:

Date of Measurement: 10/20/2009 PDOP Reading: 1.3 Instrument Operator's Name: JD Hopkins

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
1820 FNL 1935 FWL 1820 FNL 1935 FWL  
Sec: 35 Twp: 1N Rng: 98W Sec: 35 Twp: 1N Rng: 98W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 3500 ft

18. Distance to nearest property line: 1820 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1208 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Lower Sego	SEGO			
Mesa Verde	MVRD			
Rollins	RLNS			

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: 59394

22. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

☒

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
See lease attached on previous submittal.

25. Distance to Nearest Mineral Lease Line: 1820 ft 26. Total Acres in Lease: 2365

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite  
Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: \_\_\_\_\_  
If 28, 29, or 30 are "Yes" a pit permit may be required.

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	28	20	94	0	60	120	60	0
SURF	14+3/4	9+5/8	36	0	3,400	1,407	3,400	0
1ST	8+3/4	5+1/2	17	0	12,200	1,499	12,200	6,000

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments No changes from previous Form 2 submittal have occurred. This pad was built in November 2007. There will be no additional pad disturbance. This is the second well on this pad. A closed loop system will be used. No pits will be built. Cuttings will be hauled to an EPA approved landfill. Form 2A expires January 19, 2013.

34. Location ID: 316661

35. Is this application in a Comprehensive Drilling Plan? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Reed Haddock

Title: Regulatory Analyst Date: 4/4/2012 Email: rhaddock@basspet.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 4/27/2012

#### API NUMBER

05 103 11635 00

Permit Number: \_\_\_\_\_ Expiration Date: 4/26/2014

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

### **Attachment Check List**

Att Doc Num	Name
400268412	FORM 2 SUBMITTED

Total Attach: 1 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	LGD/pub. comments waived. Final Review---passed.	4/27/2012 9:51:28 AM
Permit	Current 2A expiring 1/19/2013.	4/23/2012 11:00:16 AM
Permit	Operator corrected #15 and #23. This form has passed completeness.	4/5/2012 8:50:16 AM
Permit	Returned to draft. Missing #15 and 23.	4/5/2012 7:14:11 AM

Total: 4 comment(s)

### **BMP**

<b><u>Type</u></b>	<b><u>Comment</u></b>

Total: 0 comment(s)