



E.L. Minch 24-4

05-123-33658

Sec 4 T3N R68W

Weld County, Colorado

WELLBORE SCHEMATIC (VERTICAL WELL, NOT DIRECTIONAL)

4/25/2012

PROPOSED PLUGGED &  
ABANDONED WELLBORE

Spud Date: 4/3/2012

KB: 5069'

GL: 5053'

CUT 4' BELOW  
GROUND LEVEL &  
WELD ON A PLATE

10 SX CEMENT SURFACE  
PLUG #5 FROM  
0-40 FEET

**Surface Casing:**

8 5/8" 24# J-55

Surf to 735', w/520 sx cement

Circulated 5 bbls of cement to surface

45 SX CEMENT PLUG  
"SURFACE SITOE"  
PLUG #4 FROM  
650' to 800'

**Production Casing:**

None Run-Well Dry Hole to be plugged

FORMATION  
TOPS: TOC: NA

**Tubing:**

45 SX CEMENT PLUG  
#3 FROM 3450-3600'

PARKMAN 3570'

SUSSEX 4152'

SILVERADO 4565'

**Workovers:**

45 SX CEMENT PLUG  
#2 FROM 4450-4600'

NIOBARA 7082'

FORTITUDY 7375'

Formation Perfs: (NONE)

Codell 7398'

Codell NA

45 SX CEMENT PLUG  
#1 FROM 6950-7100'

MD: 7548'

NOTE: PRODUCTION CASING NOT  
RUN, NOT CEMENTED  
7 7/8" OPEN HOLE FROM 735' TO 7548'

By: K.E. Connell  
4-25-12