

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

2286935

Date Received:

01/17/2012

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 96850

4. Contact Name: sSANDRA SALAZAR

2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

Phone: (303) 629-8456

3. Address: 1001 17TH STREET - SUITE #1200

Fax: (303) 629-8268

City: DENVER State: CO Zip: 80202

5. API Number 05-045-19556-00

6. County: GARFIELD

7. Well Name: Holl

Well Number: RWF 323-31

8. Location: QtrQtr: NWSW Section: 31 Township: 6S Range: 94W Meridian: 6

Footage at surface: Distance: 2141 feet Direction: FSL Distance: 1027 feet Direction: FWL

As Drilled Latitude: 39.480017 As Drilled Longitude: -107.934261

GPS Data:

Data of Measurement: 01/26/2011 PDOP Reading: 1.0 GPS Instrument Operator's Name: JACK KIRKPATRICK

** If directional footage at Top of Prod. Zone Dist.: 1972 feet. Direction: FSL Dist.: 1626 feet. Direction: FWL

Sec: 31 Twp: 6S Rng: 94W

** If directional footage at Bottom Hole Dist.: 1962 feet. Direction: FSL Dist.: 1616 feet. Direction: FWL

Sec: 31 Twp: 6S Rng: 94W

9. Field Name: RULISON

10. Field Number: 75400

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 07/01/2011 13. Date TD: 07/07/2011 14. Date Casing Set or D&A: 07/08/2011

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7782 TVD** 7740 17 Plug Back Total Depth MD 7395 TVD** 7353

18. Elevations GR 5351 KB 5377

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

SP/GR/HDIL/ZDL/CN AND CBL, MUD

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	18		0	104	39	0	104	VISU
SURF	13+1/2	9+5/8		0	1,115	320	0	1,115	VISU
1ST	8+3/4	4+1/2		0	7,767	1,265	3,300	7,767	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH G	1,907		<input type="checkbox"/>	<input type="checkbox"/>	
MESAVERDE	4,267		<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	6,744		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	7,724		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

FORMATION LOG INTERVALS AND TEST ZONES COMMENTS: SURFACE PRESSURE = 0#

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: SANDRA SALAZAR

Title: PERMITTING Date: 12/30/2011 Email: SANDRA.SALAZAR@WILLIAMS.COM

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
2286937	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
2286936	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
2286935	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400274446	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date
Permit	off hold--uploaded dir. template. added MUD to list of logs. all logs rec'd.	4/19/2012 3:21:10 PM
Permit	Not processed, directional template not submitted	2/16/2012 10:47:34 AM

Total: 2 comment(s)