

1625 Broadway  
Suite 2000  
Denver, CO 80202

Tel: 303.228.4000  
Fax: 303.228.4280  
www.nobleenergyinc.com



April 30, 2012

Colorado Oil and Gas Conservation Commission  
The Chancery Building  
1120 Lincoln Street, Suite 801  
Denver, CO 80203  
Attn: Mr. David Neslin, Director

RE: **Request to the Director for 318A.m. GWA Minimum Intrawell Distance Exception**  
**CON GQ07-01**  
Lyons New Drill  
Township 10 North, Range 61 West, 6th P.M.  
Section 7: NE/4NE/4: 635' FNL & 687' FEL (Surface Location)  
Weld County, Colorado

Mr. Neslin:

Noble Energy Inc. (NEI) is planning to drill the above mentioned well to the Lyons formations.

The path of NEI's proposed vertical well will be less than the 150' minimum distance from another well(s) as required by Rule 318A.m. (see wells listed below). Noble is the Operator of the encroached upon well, therefore no waiver is required. Please see Noble's Anti-Collision Mitigation BMP noted below.

MAE 41-07  
API No. 05-123-07397  
Operator: Noble Energy Inc.  
NENE Section 7, T10N-R61W, 6<sup>th</sup> P. M.

**Anti-collision:**

Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5.

Noble respectfully requests that the COGCC review the enclosed information and approve the requested exception location Application for Permit to Drill the captioned well.

Respectfully,

A handwritten signature in blue ink that reads 'Mari Clark'.

Mari Clark  
Regulatory Analyst II