

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

2285466

Date Received:

10/24/2011

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 96850 4. Contact Name: SANDRA SALAZAR
2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC Phone: (303) 629-8456
3. Address: 1001 17TH STREET - SUITE #1200 Fax: (303) 629-8268
City: DENVER State: CO Zip: 80202

5. API Number 05-045-19632-00 6. County: GARFIELD
7. Well Name: Savage Well Number: RWF 341-3
8. Location: QtrQtr: SWSE Section: 34 Township: 6S Range: 94W Meridian: 6
Footage at surface: Distance: 656 feet Direction: FSL Distance: 1807 feet Direction: FEL
As Drilled Latitude: 39.476365 As Drilled Longitude: -107.871258

GPS Data:

Data of Measurement: 11/05/2010 PDOP Reading: 2.2 GPS Instrument Operator's Name: JACK KIRKPATRICK

** If directional footage at Top of Prod. Zone Dist.: 326 feet. Direction: FNL Dist.: 645 feet. Direction: FEL

Sec: 3 Twp: 7S Rng: 94W

** If directional footage at Bottom Hole Dist.: 335 feet. Direction: FNL Dist.: 647 feet. Direction: FEL

Sec: 3 Twp: 7S Rng: 94W

9. Field Name: RULISON 10. Field Number: 75400

11. Federal, Indian or State Lease Number: COC 0007506

12. Spud Date: (when the 1st bit hit the dirt) 05/07/2011 13. Date TD: 05/13/2011 14. Date Casing Set or D&A: 05/15/2011

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7960 TVD** 7674 17 Plug Back Total Depth MD 7916 TVD** 7630

18. Elevations GR 5626 KB 5652

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

RPM AND CBL, MUD

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	18		0	95	36	0	95	VISU
SURF	13+1/2	9+5/8		0	1,165	320	0	1,165	VISU
1ST	8+3/4	4+1/2		0	7,949	1,320	2,400	7,949	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH G	1,596		<input type="checkbox"/>	<input type="checkbox"/>	
MESAVERDE	4,333		<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	7,026		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	7,868		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

FORM 5A DOC #2285469

FORMATION LOG INTERVALS AND TEST ZONES COMMENTS: SURFACE PRESSURE = 0#

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: SANDRA SALAZAR

Title: PERMITTING

Date: 9/30/2011

Email: SANDRA.SALAZAR@WILLIAMS.COM

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
2285468	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
2285467	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
2285466	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date
Permit	approved w/out paper RPM log--WPX submitting soon.	4/18/2012 11:26:52 AM
Permit	MISSING RPM LOG - NOT REQUESTED PER J.S., REQ MWD/FMI LOGS	12/5/2011 10:36:35 AM

Total: 2 comment(s)