

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400279162

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 47120

4. Contact Name: JOEL MALEFYT

2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

Phone: (720) 929-6828

3. Address: P O BOX 173779

Fax: (720) 929-7828

City: DENVER State: CO Zip: 80217-

5. API Number 05-123-33793-00

6. County: WELD

7. Well Name: STREAR

Well Number: 35-10

8. Location: QtrQtr: SESW Section: 10 Township: 2N Range: 67W Meridian: 6

Footage at surface: Distance: 1251 feet Direction: FSL Distance: 1364 feet Direction: FWL

As Drilled Latitude: 40.148892 As Drilled Longitude: -104.881050

GPS Data:

Data of Measurement: 04/04/2012 PDOP Reading: 1.4 GPS Instrument Operator's Name: Renee Doiron

** If directional footage at Top of Prod. Zone Dist.: 28 feet. Direction: FSL Dist.: 1307 feet. Direction: FWL

Sec: 10 Twp: 2N Rng: 67W

** If directional footage at Bottom Hole Dist.: 21 feet. Direction: FSL Dist.: 1309 feet. Direction: FWL

Sec: 10 Twp: 2N Rng: 67W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 03/21/2012 13. Date TD: 03/23/2012 14. Date Casing Set or D&A: 03/24/2012

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 8327 TVD** 8168 17 Plug Back Total Depth MD 8294 TVD** 8135

18. Elevations GR 4973 KB 4988

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL; NO OPEN HOLE LOGS RUN

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24	0	706	450	15	706	CALC
1ST	7+7/8	4+1/2	11.6	0	8,317	45	8,088	8,317	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: 03/24/2012					
Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
DV TOOL	1ST	8,050	1,017	958	8,050
Details of work:					

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES					
FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	4,208	4,408	<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,628	4,978	<input type="checkbox"/>	<input type="checkbox"/>	
SHANNON	5,170	5,290	<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,480		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,700		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,708		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	8,167		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JOEL MALEFYT

Title: REGULATORY ANALYST Date: _____ Email: JOEL.MALEFYT@ANADARKO.COM

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400279356	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400279354	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400279373	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)