

FORM  
2

Rev  
12/05

# State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400271054

Date Received:

## APPLICATION FOR PERMIT TO:

1.  Drill,  Deepen,  Re-enter,  Recomplete and Operate

### 2. TYPE OF WELL

OIL  GAS  COALBED  OTHER \_\_\_\_\_  
SINGLE ZONE  MULTIPLE  COMMINGLE

Refiling

Sidetrack

PluggingBond SuretyID

20090078

3. Name of Operator: PETROLEUM DEVELOPMENT CORPORATION

4. COGCC Operator Number: 69175

5. Address: 1775 SHERMAN STREET - STE 3000

City: DENVER State: CO Zip: 80203

6. Contact Name: Liz Lindow Phone: (303)831-3974 Fax: ( )

Email: llindow@petd.com

7. Well Name: Riteaway Well Number: 32E-323

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 11401

### WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 32 Twp: 5N Rng: 67W Meridian: 6

Latitude: 40.362770 Longitude: -104.920250

Footage at Surface: 242 feet FNL 1746 feet FNL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 4794 13. County: WELD

### 14. GPS Data:

Date of Measurement: 03/01/2012 PDOP Reading: 1.5 Instrument Operator's Name: Ben Adsit

15. If well is  Directional  Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: 500 FNL 500 FNL Bottom Hole: 500 FSL 500 FNL  
Sec: 32 Twp: 5N Rng: 67W Sec: 32 Twp: 5N Rng: 67W

16. Is location in a high density area? (Rule 603b)?  Yes  No

17. Distance to the nearest building, public road, above ground utility or railroad: 270 ft

18. Distance to nearest property line: 280 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 130 ft

### 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR		160	W2W2

21. Mineral Ownership:  Fee  State  Federal  Indian Lease #: \_\_\_\_\_

22. Surface Ownership:  Fee  State  Federal  Indian

23. Is the Surface Owner also the Mineral Owner?  Yes  No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease?  Yes  No

23b. If 23 is No:  Surface Owners Agreement Attached or  \$25,000 Blanket Surface Bond  \$2,000 Surface Bond  \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

W2NW, N2SW, S2SW of Section 32 T5N R 67W

25. Distance to Nearest Mineral Lease Line: 500 ft

26. Total Acres in Lease: 240

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated?  Yes  No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling?  Yes  No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling?  Yes  No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)?  Yes  No

31. Mud disposal:  Offsite  Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method:  Land Farming  Land Spreading  Disposal Facility Other: Closed loop

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	875	730	875	0
1ST	8+3/4	7	26	0	7,485	650	7,485	600
1ST LINER	6+1/8	4+1/2	11.6	6273	11,401			

32. BOP Equipment Type:  Annular Preventer  Double Ram  Rotating Head  None

33. Comments Conductor casing will not be used. Operator requests an exception location per rule 318Aa and rule 318Ac: well will not be drilled in a legal drilling window or twinned with an existing well. Waviers attached. Per rule 318Ae, the Operator requests the proposed spacing unit consisting of 160 acres, W2W2 of Sec 32 T5N R67W. Proposed spacing unit map and 30-day certificate is attached.

34. Location ID: 322682

35. Is this application in a Comprehensive Drilling Plan ?  Yes  No

36. Is this application part of submitted Oil and Gas Location Assessment ?  Yes  No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Liz Lindow

Title: Permit Representative Date: \_\_\_\_\_ Email: llindow@petd.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

\_\_\_\_\_

### Attachment Check List

Att Doc Num	Name
400271100	WELL LOCATION PLAT
400271102	EXCEPTION LOC WAIVERS
400271103	30 DAY NOTICE LETTER
400271106	TOPO MAP
400271126	EXCEPTION LOC REQUEST
400271127	PROPOSED SPACING UNIT
400280001	DIRECTIONAL DATA
400280002	DEVIATED DRILLING PLAN
400280018	EXCEPTION LOC REQUEST

Total Attach: 9 Files

### General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)

### BMP

<u>Type</u>	<u>Comment</u>
Drilling/Completion Operations	<p>Wellbore Fracturing Stimulation</p> <ol style="list-style-type: none"> <li>1. At least seven (7) days prior to fracture stimulation, the operator is to notify all operators of non-operated wells within 300 feet of the wellbore to be fracture stimulated of the anticipated stimulation date and the recommended best management practice to shut-in all wells within 300' of the stimulated wellbore completed in the same formation.</li> <li>2. The operator will monitor the bradenhead pressure of all wells within 300 feet of the well to be fracture stimulated.</li> <li>3. Bradenhead pressure gauges are to be installed 24 hours prior to stimulation. The gauges are to read at least once during every 24-hour period until 24-hours after stimulation is completed (post flowback). The gauges are to be of the type able to read current pressure and record the maximum encountered pressure in a 24-hour period. The gauge is to be reset between each 24-hour period. The pressures are to be recorded and saved. Alternate electronic measurement may be used to record the prescribed pressures. Data shall be kept for a period of one year.</li> <li>4. If at any time during stimulation or the 24-hour post-stimulation period, the bradenhead annulus pressure of the treatment well or offset wells increases more than 200 psig, as per Rule 341, the operator of the well being stimulated shall verbally notify the Director as soon as practicable, but no later than twenty-four (24) hours following the incident. Within fifteen (15) days after the occurrence, the operator shall submit a Sundry Notice, Form 4, giving all details, including corrective actions taken.</li> </ol>
Drilling/Completion Operations	<p>Anti-Collision</p> <p>Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5.</p>

Total: 2 comment(s)