



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 600305

Date	1/19/12	Well Owner	Kerr McGee	Well No.	19-1	Lease	Dechant
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (Xtreme #14)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth	FL 734				
Surface	8 5/8" CSE-24"	Bottom of Surface	FL 724				
Plug		Plug Landed @	681	Ft.	Time On	2300	
Production		Pipe Landed @	724	Ft.	Plug Down	0400	
Description	Qty.	Meas.	Unit Price	Amount			
Set Up Charge	1						
Cement Neat	✓ Type III	460	SKS				
Poz. Mix	MIKE LINGREEN						
Calcium Chloride	User ID ZMDL6	2.5	%				
Gel %	Fio-Cete 1/4 # Per Sack						
Mileage Charge	WBSA/WO/CC 2049797.121	132	Miles				
Fuel Surcharge	G/L Acct. 800.12090	132	Miles				
Additional Cement			SKS				
Mixing Rate	4 BPM	Pre-Flush	0322-	0328			
Disp. Rate	5 BPM	Mixing	0328-	0348			
Slurry Vol.	1.32³ Cu. Ft./Sk	Change Valves	0348-	0351			
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0351-	0400			
Water/Cement	6.25 Gal/SK						
Water Temp.	60°F						
Total Slurry Vol.	108.1	BBLS Cement					
Landed Plug @	350	PSI/Final Lift @	150	PSI			
Pre-Flush Wt	30	BBLS H²O	Tax Reference Code	Sub Total			
Displace Wt	43.3	BBLS H²O	State CO 2.9%	Tax			
Circulate	4	BBLS Cement		Total			
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1208		Pump Truck		44			
1214/1216		Bulk Truck		44/44			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Steve, Chris & Evan

Received By

Cody Sanders  
Customer or His Agent