



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600425

Date	03-17-12	Well Owner	Kerr McGee	Well No.	19-10	Lease	STREAR
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME #14)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	717		
Surface	8 5/8" CSG-24"	Bottom of Surface		Fl.	706		
Plug		Plug Landed @	662	Fl.	Time On	1250	
Production		Pipe Landed @	706	Fl.	Plug Down	1545	
Description		Qty.	Meas.	Unit Price	Amount		
Set Up Charge		1					
Cement Neat	TYPE III	450	SKS				
Poz. Mix							
Calcium Chloride		2.5	%				
Gel % Flo-Cete 1/4 # Per Sack							
Mileage Charge		144	Miles				
Fuel Surcharge		144	MILES				
Additional Cement			SKS				
Mixing Rate	4 BPM	Pre-Flush	1509	1514			
Disp. Rate	5 BPM	Mixing	1514	1534			
Slurry Vol.	1.32 ³ Cu. Ft./Sk	Change Valves	1534	1537			
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1537	1545			
Water/Cement	6.25 Gal/SK						
Water Temp.	64° F						
Total Slurry Vol.	105.7	BBLS Cement					
Landed Plug @	400	PSI/Final Lift @	200	PSI			
Pre-Flush W/	20	BBLS H ₂ O	Tax Reference Code	Sub Total			
Displace W/	42.1	BBLS H ₂ O	State CO 2.9%	Tax			
Circulate	5	BBLS Cement		Total			
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1208		Pump Truck		48			
1207/1216		Bulk Truck		48/48			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JUSTIN, EVAN, CHRIS

Received By

Customer or His Agent