



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600223

Date <u>11/6/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>2C-23HZ</u>	Lease <u>Powers</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (X-treme #6)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Fl.	<u>950</u>
<u>Surface</u>	<u>9 5/8" CG-30" 13 1/2" Hole</u>	Bottom of Surface	Fl. <u>934</u>
Plug	Plug Landed @ <u>890</u>	Fl.	Time On <u>2300</u>
Production	Pipe Landed @ <u>934</u>	Fl.	Plug Down <u>0645</u>

Description	Qty.	Mess.
Set Up Charge	1	
Cement Neat <u>✓ Type III 100% EXCESS</u>	700	SKS
Poz. Mix		
Calcium Chloride	2.5	%
Gel % Flo-Cete 1/4" # Per Sack		
Mileage Charge	198	Miles
Fuel Surcharge	198	Miles
Additional Cement <u>2056/31 DRL</u>	40	SKS
Mixing Rate 4 BPM	Pre-Flush	<u>0558-0558</u>
Disp. Rate 5 BPM	Mixing	<u>0558-0628</u>
Slurry Vol. 1.32 Cu.Ft./Sk	Change Valves	<u>0628-0631</u>
Slurry Wt. 14.8 - 15.0 PPG	Displacement	<u>0631-0645</u>
Water/Cement 6.25 Gal/SK		
Water Temp. <u>52° F</u>		
Total Slurry Vol. <u>174</u>	BBLS Cement	
Landed Plug @ <u>500</u>	PSI/Final Lift @ <u>300</u>	PSI
Pre-Flush Wt <u>30</u>	BBLS H ₂ O	Tax Reference Code
Displace Wt <u>68.7</u>	BBLS H ₂ O	State CO 2.9%
Circulate <u>6</u>	BBLS Cement	Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>66</u>			
<u>1217/1218</u>		Bulk Truck		<u>66/66</u>			