

FORM
5Rev
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400241568

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 47120

4. Contact Name: JOEL MALEFYT

2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

Phone: (720) 929-6828

3. Address: P O BOX 173779

Fax: (720) 929-7828

City: DENVER State: CO Zip: 80217-

5. API Number 05-123-34286-00

6. County: WELD

7. Well Name: CANNON

Well Number: 1N-11HZ

8. Location: QtrQtr: SESE Section: 11 Township: 2N Range: 66W Meridian: 6

Footage at surface: Distance: 502 feet Direction: FSL Distance: 548 feet Direction: FEL

As Drilled Latitude: 40.146999 As Drilled Longitude: -104.736816

GPS Data:

Data of Measurement: 02/14/2012 PDOP Reading: 2.6 GPS Instrument Operator's Name: RENEE DOIRON

** If directional footage at Top of Prod. Zone Dist.: 713 feet. Direction: FSL Dist.: 679 feet. Direction: FEL

Sec: 11 Twp: 2N Rng: 66W

** If directional footage at Bottom Hole Dist.: 468 feet. Direction: FNL Dist.: 514 feet. Direction: FEL

Sec: 11 Twp: 2N Rng: 66W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 12/20/2011 13. Date TD: 12/29/2011 14. Date Casing Set or D&A: 01/01/2012

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 11773 TVD** 7263 17 Plug Back Total Depth MD 11773 TVD** 7263

18. Elevations GR 5038 KB 5055

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

LWD, MUD, OH, FMI, CBL

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	13+1/2	9+5/8	36	0	934	690	0	940	CALC
1ST	8+3/4	7+0/0	26	0	7,657	750	0	7,660	CALC
1ST LINER	6+1/8	4+1/2	11.6	6664	11,758				CALC

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SHARON SPRINGS	7,231		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,362		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: JOEL MALEFYTTitle: REGULATORY ANALYST

Date: _____

Email: JOEL.MALEFYT@ANADARKO.COM**Attachment Check List**

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400255399	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400255390	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400255391	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments**User Group****Comment****Comment Date**

--	--	--

Total: 0 comment(s)